### STORM WATER MANAGEMENT PLAN

(Major SWMP)

For

Starco Gas Station & Food Mart S06-026 LOG No. 06-19-021

> 9561 Jamacha Blvd Spring Valley, CA

Prepared By
K & S ENGINEERING
7801 MISSION CENTER COURT,
SUITE 100
SAN DIEGO, CA 92108

For Jamacha Group Inc.

Date:May 18, 2006 Revision:January 22, 2007

### Storm Water Management Plan For Priority Projects (Major SWMP)

Project Name:	Starco Food Mart
Permit Number (Land Development Projects):	
Work Authorization Number (CIP):	
Applicant:	Jamacha Group Inc.
Applicant's Address:	9561 Jamacha Blvd
Plan Prepare By (Leave blank if same as	K & S Engineering
applicant):	
Date:	May 17, 2006
Revision Date (If applicable):	

The County of San Diego Watershed Protection, Storm Water Management, and Discharge Control Ordinance (WPO) (Ordinance No. 9424) requires all applications for a permit or approval associated with a Land Disturbance Activity must be accompanied by a Storm Water Management Plan (SWMP) (section 67.804.f). The purpose of the SWMP is to describe how the project will minimize the short and long-term impacts on receiving water quality. Projects that meet the criteria for a priority project are required to prepare a Major SWMP.

Since the SWMP is a living document, revisions may be necessary during various stages of approval by the County. Please provide the approval information requested below.

Project Review Stage		e SWMP visions?	If YES, Provide Revision Date
	YES	NO	ACVISION Dute
First stage		X	
3	/		

### PROJECT DESCRIPTION

The project site consist of 0.54 acres(previously mass garded) and is located north of Jamacha Blvd in the County of San Diego (see attachment A). The project is approximately 0.6 mile of the Sweetwater Reservoir. The project area is characterized by moderately sloping land. The proposed development consist of one food center building, retail fuel pumps, parking spaces, lanscaping and irrigation.

### PRIORITY PROJECT DETERMINATION

Please check the box that best describes the project. Does the project meet one of the following criteria?

criteria? PRIORITY PROJECT	YES	NO
Redevelopment within the County Urban Area that creates or adds at least 5,000	X	
Redevelopment within the County Orban Area that creates of data at tensory,		
net square feet of additional impervious surface area		X
Residential development of more than 10 units		X
Commercial developments with a land area for development of greater than		11
100,000 square feet		X
Automotive repair shops		$\frac{X}{X}$
Restaurants, where the land area for development is greater than 5.000 square		Λ
feet		X
Hillside development, in an area with known erosive soil conditions, where there		Λ
will be grading on any natural slope that is twenty-five percent or greater, if the		
development creates 5,000 square feet or more of impervious surface		37
Environmentally Sensitive Areas: All development and redevelopment located		X
within or directly adjacent to or discharging directly to an environmentally		
sensitive area (where discharges from the development or redevelopment will		
enter receiving waters within the environmentally sensitive area), which either		
creates 2.500 square feet of impervious surface on a proposed project site or		
increases the area of imperviousness of a proposed project site to 10% or more of		
its naturally occurring condition.		
Parking Lots 5,000 square feet or more or with 15 parking spaces or more and	V-1	X
notentially exposed to urban runoff		***
Streets, roads, highways, and freeways which would create a new paved surface		X
that is 5,000 square feet or greater		

**Limited Exclusion:** Trenching and resurfacing work associated with utility projects are not considered priority projects. Parking lots, buildings and other structures associated with utility projects are subject to SUSMP requirements if one or more of the criteria above are met.

If you answered **NO** to all the questions, then **STOP**. Please complete a Minor SWMP for your project.

If you answered YES to any of the questions, please continue.

The following questions provide a guide to collecting information relevant to project stormwater quality issues. Please provide a description of the findings in text box below.

1. Describe the topography of the project area.  2. Describe the local land use within the project area and adjacent areas.  3. Evaluate the presence of dry weather flow.  4. Determine the receiving waters that may be affected by the project throughout the project life cycle (i.e., construction, maintenance and operation).  5. For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.  6. Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D	qual	quality issues. Please provide a description of the findings in text box below.  COMPLETED NA									
<ol> <li>Describe the topography of the project area.</li> <li>Describe the local land use within the project area and adjacent areas.</li> <li>Evaluate the presence of dry weather flow.</li> <li>Determine the receiving waters that may be affected by the project throughout the project life cycle (i.e., construction, maintenance and operation).</li> <li>For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.</li> <li>Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.</li> <li>Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.</li> <li>Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.</li> <li>If considering Treatment BMPs, determine the soil classification, soil Type D</li> </ol>		QUESTIONS	COMPLETED	INA							
2. Describe the local land use within the project area and adjacent areas.  3. Evaluate the presence of dry weather flow.  4. Determine the receiving waters that may be affected by the project throughout the project life cycle (i.e., construction, maintenance and operation).  5. For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.  6. Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D	1.	Describe the topography of the project area.	Flat/w 4'Slope								
<ol> <li>Evaluate the presence of dry weather flow.</li> <li>Determine the receiving waters that may be affected by the project throughout the project life cycle (i.e., construction, maintenance and operation).</li> <li>For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.</li> <li>Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.</li> <li>Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.</li> <li>Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.</li> <li>If considering Treatment BMPs, determine the soil classification,</li> </ol>		Describe the local land use within the project area and adjacent	Commercial								
<ol> <li>Evaluate the presence of dry weather flow.</li> <li>Determine the receiving waters that may be affected by the project throughout the project life cycle (i.e., construction, maintenance and operation).</li> <li>For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.</li> <li>Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.</li> <li>Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.</li> <li>Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.</li> <li>If considering Treatment BMPs, determine the soil classification,</li> </ol>				Х							
<ol> <li>Determine the receiving waters that may be affected by the project throughout the project life cycle (i.e., construction, maintenance and operation).</li> <li>For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.</li> <li>Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.</li> <li>Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.</li> <li>Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.</li> <li>If considering Treatment BMPs, determine the soil classification, soil Type D</li> </ol>	3.	Evaluate the presence of dry weather flow.		Λ							
throughout the project life cycle (i.e., construction, maintenance and operation).  5. For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.  6. Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, soil Type D	4.	Determine the receiving waters that may be affected by the project									
and operation).  5. For the project limits, list the 303(d) impaired receiving water bodies and their constituents of concern.  6. Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D		throughout the project life cycle (i.e., construction, maintenance	Reserver								
bodies and their constituents of concern.  6. Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D		and operation).									
bodies and their constituents of concern.  6. Determine if there are any High Risk Areas (municipal or domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D	5.	For the project limits, list the 303(d) impaired receiving water									
domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D		bodies and their constituents of concern.	Metals								
domestic water supply reservoirs or groundwater percolation facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D	6.	Determine if there are any High Risk Areas (municipal or	No								
facilities) within the project limits.  7. Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D		domestic water supply reservoirs or groundwater percolation	110								
<ol> <li>Determine the Regional Board special requirements, including TMDLs, effluent limits, etc.</li> <li>Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.</li> <li>If considering Treatment BMPs, determine the soil classification, Soil Type D</li> </ol>		facilities) within the project limits.									
TMDLs, effluent limits, etc.  8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, soil Type D	7.	Determine the Regional Board special requirements, including		х							
8. Determine the general climate of the project area. Identify annual rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D		TMDLs, effluent limits, etc.									
rainfall and rainfall intensity curves.  9. If considering Treatment BMPs, determine the soil classification, Soil Type D	8.	Determine the general climate of the project area. Identify annual									
9. If considering Treatment BMPs, determine the soil classification, Soil Type D		rainfall and rainfall intensity curves.	6Hr2.9 24hr 5.8								
	9.	If considering Treatment BMPs, determine the soil classification,	Soil Type D								
permeability, erodibility, and depth to groundwater.		permeability, erodibility, and depth to groundwater.									
10. Determine contaminated or hazardous soils within the project area. None	10	Determine contaminated or hazardous soils within the project area.	None								

The project is located in the Sweetwater-Middle Jamacha water shed 909.21 The area is currently in a previously mass graded vacant lot and is characterized by small grass and shrubs. Eventually the Overland runoff the site drains into Sweetwater Reservoir via public storm drain system. Within the site there is some possible coliform bacteria.

Complete the checklist below to determine if Treatment Best Management Practices (BMPs) are required for the project.

No.	CRITERIA	YES	NO	INFORMATION
1	Is this an emergency project		Х	If YES, go to 6. If NO, continue to 2.
2.	Have TMDLs been established		Х	If YES, go to 5.

No.	CRITERIA	YES	NO	INFORMATION
1101	for surface waters within the			If NO, continue to 3.
	project limit?			
3.	Will the project directly			If YES, go to 5.
	discharge to a 303(d) impaired		Х	If NO, continue to 4.
	receiving water body?			
4.	Is this project within the urban	x		If YES, continue to 5.
	and environmentally sensitive	A		If NO, go to 6.
	areas as defined on the maps in			
	Appendix B of the County of			
	San Diego Standard Urban			
	Storm Water Mitigation Plan			
	for Land Development and			
	Public Improvement Projects?			707770
5.	Consider approved Treatment	х		If YES, go to 7.
	BMPs for the project.			0 D : FIL 1
6.	Project is not required to			Document for Project Files by
	consider Treatment BMPs			referencing this checklist.
7.	End			

### WATERSHED

### Please provide the hydrologic sub-area and number(s)

Number	Name
909.21	Middle Sweetwater

SURFACE WATERS	Hydrologic Unit Basin Number	MUN	AGR	IND	PROC	GWR	FRESH	POW	REC1	REC2	BIOL	WARM	COLD	WILD	RARE	SPWN
Inland Surface Waters																
909.21		0		X					X	X	X	X		X		
<b>Ground Waters</b>																
909.21		X	X	X	О											

X Existing Beneficial Use

### POLLUTANTS OF CONCERN

Using Table 1, identify pollutants that are anticipated to be generated from the proposed priority project categories. Pollutants associated with any hazardous material sites that have been remediated or are not threatened by the proposed project are not considered a pollutant of concern.

Table 1. Anticipated and Potential Pollutants Generated by Land Use Type

Table 1.	Anticipated	l and Poten	tiai Poiit	itants Gener	ateu by L	and Osc 1	<del>, , , , , , , , , , , , , , , , , , , </del>		
				General l	Pollutant C	Categories			
Priority Project Categories	Sediments	Nutrients	Heavy Metals	Organic Compounds	Trash & Debris	Oxygen Demanding Substances	Oil & Grease	Bacteria & Viruses	Pesticides
Detached Residential Development									
Attached Residential Development									
Commercial Development >100,000 ft <sup>2</sup>	P <sup>(1)</sup>	P <sup>(1)</sup>		P <sup>(2)</sup>	X	P <sup>(5)</sup>	X	P <sup>(3)</sup>	P <sup>(5)</sup>
Automotive Repair Shops									
Restaurants									
Hillside Development >5,000 ft <sup>2</sup>									

<sup>0</sup> Potential Beneficial Use

<sup>\*</sup> Excepted from Municipal

				General 1	Pollutant C	ategories		T	
Priority Project Categories Parking Lots	Sediments P(1)	Nutrients P <sup>(1)</sup>	Heavy Metals	Organic Compounds	Trash & Debris	Oxygen Demanding Substances P <sup>(1)</sup>	Oil & Grease	Bacteria & Viruses	Pesticides P(1)
Streets, Highways & Freeways	X	P <sup>(1)</sup>	X	X <sup>(4)</sup>	X	P <sup>(5)</sup>	X		

X = anticipated

- (1) A potential pollutant if landscaping exists on-site.
- (2) A potential pollutant if the project includes uncovered parking areas.
- (3) A potential pollutant if land use involves food or animal waste products.
- (4) Including petroleum hydrocarbons.
- (5) Including solvents.

**Note:** If other monitoring data that is relevant to the project is available. Please include as Attachment C.

### **CONSTRUCTION BMPs**

Please check the construction BMPs that may be used. The BMPs selected are those that will be implemented during construction of the project. The applicant is responsible for the placement and maintenance of the BMPs selected.

an	d maintenance of the Divir's science.									
X	Silt Fence		Desilting Basin							
	Fiber Rolls	X	Gravel Bag Berm							
	Street Sweeping and Vacuuming		Sandbag Barrier							
X	Storm Drain Inlet Protection	X	Material Delivery and Storage							
	Stockpile Management	X	Spill Prevention and Control							
	Solid Waste Management	X	Concrete Waste Management							
X	Stabilized Construction Entrance/Exit	X	Water Conservation Practices							
	Dewatering Operations		Paving and Grinding Operations							
	Vehicle and Equipment Maintenance									

### SITE DESIGN

To minimize stormwater impacts, site design measures must be addressed. The following checklist provides options for avoiding or reducing potential impacts during project planning. If

P = potential

		OPTIONS	YES	NO	N/A
1.	to rec proble	he project be relocated or realigned to avoid/reduce impacts eiving waters or to increase the preservation of critical (or ematic) areas such as floodplains, steep slopes, wetlands, and with erosive or unstable soil conditions?		X	
2.	Can the project be designed to minimize impervious footprint?			X	
3.	Conserve natural areas where feasible?			X	
4.	walky	e landscape is proposed, can rooftops, impervious sidewalks, ways, trails and patios be drained into adjacent landscaping?		Х	
5.	For ro	padway projects, can structures and bridges be designed or ed to reduce work in live streams and minimize construction ets?		X	
6.	Can any of the following methods be utilized to minimize erosion from slopes:			X	
	6.a.	Disturbing existing slopes only when necessary?	X	1100	
	6.b.	Minimize cut and fill areas to reduce slope lengths?	X		
	6.c.	Incorporating retaining walls to reduce steepness of slopes or to shorten slopes?	X		
	6.d.	Providing benches or terraces on high cut and fill slopes to reduce concentration of flows?			X
	6.e.	Rounding and shaping slopes to reduce concentrated flow?		X	
	6.f.	Collecting concentrated flows in stabilized drains and channels?		X	

Please provide a brief explanation for each option that was checked N/A or NO in the following box.

The project can't be relocated, currently the vacant lot is a flat surface with a 4'Max. of slope. This drainage insert has low removal efficiency and has been implemented due to the lack and limited space to proposed other and more efficient bmp's such as filtration, detention basins, biofilters and wet ponds.

If the project includes work in channels, then complete the following checklist. Information shall be obtained from the project drainage report.

No.	CRITERIA	YES	NO	N/A	COMMENTS
	Will the project increase velocity or volume of			X	If YES go to 5.
	downstream flow?				
2.	Will the project discharge to unlined channels?			X	If YES go to 5.
3.	Will the project increase potential sediment load			X	If YES go to 5.

No.	CRITERIA	YES	NO	N/A	COMMENTS
1,00	of downstream flow?				
4.	Will the project encroach, cross, realign, or cause other hydraulic changes to a stream that may affect upstream and/or downstream channel stability?			X	If YES go to 7.
5.	Review channel lining materials and design for stream bank erosion.			Х	Continue to 6.
6.	Consider channel erosion control measures within the project limits as well as downstream. Consider scour velocity.			X	Continue to 7.
7.	Include, where appropriate, energy dissipation devices at culverts.			х	Continue to 8.
8.	Ensure all transitions between culvert outlets/headwalls/wingwalls and channels are smooth to reduce turbulence and scour.			х	Continue to 9.
9.	Include, if appropriate, detention facilities to reduce peak discharges.			х	
10.	"Hardening" natural downstream areas to prevent erosion is not an acceptable technique for protecting channel slopes, unless predevelopment conditions are determined to be so erosive that hardening would be required even in the absence of the proposed development.			X	Continue to 11.
11.	Provide other design principles that are comparable and equally effective.			X	Continue to 12.
12.	End			X	

### SOURCE CONTROL

Please complete the following checklist for Source Control BMPs. If the BMP is not applicable for this project, then check N/A only at the main category.

101	tnis pro	YES	NO	N/A	
1.	Provi				
<u> </u>	1.a.	de Storm Drain System Stenciling and Signage  All storm drain inlets and catch basins within the project area shall have	X		
		a stencil or tile placed with prohibitive language (such as: "NO			
	ŀ	DUMPING – DRAINS TO THE OCEAN ") and/or graphical icons to	į.		
		discourage illegal dumping.			
	1.b.	Signs and prohibitive language and/or graphical icons, which prohibit			X
		illegal dumping, must be posted at public access points along channels			
		and creeks within the project area.			
2.	Desig	n Outdoors Material Storage Areas to Reduce Pollution Introduction			
	2.a.	This is a detached single-family residential project. Therefore, personal			X
		storage areas are exempt from this requirement.			

		ВМР	YES	NO	N/A
	2.b.	Hazardous materials with the potential to contaminate urban runoff shall			X
		either be: (1) placed in an enclosure such as, but not limited to, a			
		cabinet shed or similar structure that prevents contact with runoff or			
		spillage to the storm water conveyance system; or (2) protected by			
		secondary containment structures such as berms, dikes, or curbs.			
	2.c.	The storage area shall be paved and sufficiently impervious to contain			X
	2.0.	leaks and spills.			
	2.d.	The storage area shall have a roof or awning to minimize direct			X
	2. <b>u</b> .	precipitation within the secondary containment area.			
	D	n Trash Storage Areas to Reduce Pollution Introduction			
		Paved with an impervious surface, designed not to allow run-on from	x		
	3.a.	Paved with an impervious surface, designed not to anow run on from	1-		
ŀ		adjoining areas, screened or walled to prevent off-site transport of trash;			
		or,	X		
	3.b.	Provide attached lids on all trash containers that exclude rain, or roof or	Α		
		awning to minimize direct precipitation.			
.	Use E	Efficient Irrigation Systems & Landscape Design			
	The f	ollowing methods to reduce excessive irrigation runoff shall be			
	consi	dered, and incorporated and implemented where determined applicable			
l		easible.			
	4.a.	Employing rain shutoff devices to prevent irrigation after precipitation.	X		
	4.b.	Designing irrigation systems to each landscape area's specific water	X		
		requirements.			
	4.c.	Using flow reducers or shutoff valves triggered by a pressure drop to	X		
l	1.0.	control water loss in the event of broken sprinkler heads or lines.			
	4.d.	Employing other comparable, equally effective, methods to reduce	x		
	4.u.	irrigation water runoff.			
.	Duite	ite Roads			
	The	lesign of private roadway drainage shall use at least one of the following			
		Rural swale system: street sheet flows to vegetated swale or gravel			х
	5.a.	Rural swale system: sheet sheet hows to regulated swale of graves			
		shoulder, curbs at street corners, culverts under driveways and street			
		crossings.			X
	5.b.	Urban curb/swale system: street slopes to curb, periodic swale inlets			^
		drain to vegetated swale/biofilter.			v
	5.c.	Dual drainage system: First flush captured in street catch basins and			X
		discharged to adjacent vegetated swale or gravel shoulder, high flows			
		connect directly to storm water conveyance system.		<u> </u>	
	5.d.	Other methods that are comparable and equally effective within the			X
		project.			
	Resid	lential Driveways & Guest Parking			
	The d	esign of driveways and private residential parking areas shall use one at			
	least o	of the following features.			
$\neg$	6.a.	Design driveways with shared access, flared (single lane at street) or			X
	o.u.	wheelstrips (paving only under tires); or, drain into landscaping prior to			
		discharging to the storm water conveyance system.			
$\dashv$	6 h	Uncovered temporary or guest parking on private residential lots may			X
	6.b.	be: paved with a permeable surface; or, designed to drain into			
		landscaping prior to discharging to the storm water conveyance system.			
		Other features which are comparable and equally effective.	1		X
	6.c.	1 Out 1 Continue and into any comparable and administrations		1	

		ВМР	YES	NO	N/A
	Loadi	ng/unloading dock areas shall include the following.			
	7.a.			X	
		Cover loading dock areas, or design drainage to preclude urban run-on and runoff.			
	7.b.	Direct connections to storm drains from depressed loading docks (truck			X
		wells) are prohibited.			
	7.c.	Other features which are comparable and equally effective.			
8.		tenance Bays			
		enance bays shall include the following.			
	8.a.	Repair/maintenance bays shall be indoors; or, designed to preclude			X
		urban run-on and runoff.			
	8.b.	Design a repair/maintenance bay drainage system to capture all wash			X
		water leaks and spills. Connect drains to a sump for collection and			
		disposal. Direct connection of the repair/maintenance bays to the storm			
		drain system is prohibited. If required by local jurisdiction, obtain an			
		Industrial Waste Discharge Permit.			
	8.c.	Other features which are comparable and equally effective.			
9.	Vehic	le Wash Areas		<u> </u>	
	Priori	ty projects that include areas for washing/steam cleaning of vehicles shall			
		e following.		<u> </u>	
	9.a.	Self-contained; or covered with a roof or overhang.			X
	9.b.	Equipped with a clarifier or other pretreatment facility.			X
	9.c.	Properly connected to a sanitary sewer.			X
	9.d.	Other features which are comparable and equally effective.			X
10.	Outd	oor Processing Areas			
	Outdo	or process equipment operations, such as rock grinding or crushing,			Х
	nainti	ng or coating, grinding or sanding, degreasing or parts cleaning, waste			
	niles	and wastewater and solid waste treatment and disposal, and other			
	opera	tions determined to be a potential threat to water quality by the County			
	shall a				
	10.a.	Cover or enclose areas that would be the most significant source of			
		pollutants; or, slope the area toward a dead-end sump; or, discharge to			X
		the sanitary sewer system following appropriate treatment in accordance			
		with conditions established by the applicable sewer agency.			
	10.b.	Grade or berm area to prevent run-on from surrounding areas.			X
	10.c.	Installation of storm drains in areas of equipment repair is prohibited.			X
	10.d.	Other features which are comparable or equally effective.			
11.	Equip	oment Wash Areas		-	
	Outdo	or equipment/accessory washing and steam cleaning activities shall be.			X
	11.a.	Be self-contained; or covered with a roof or overhang.			X
	11.b.	Be equipped with a clarifier, grease trap or other pretreatment facility, as			X
		appropriate			ļ <u>.</u>
	11.c.	Be properly connected to a sanitary sewer.			X
	11.d.	Other features which are comparable or equally effective.			Х
12.	Parki	ng Areas			
	The fo	ollowing design concepts shall be considered, and incorporated and			
	imple	mented where determined applicable and feasible by the County.			
	12.a.	Where landscaping is proposed in parking areas, incorporate landscape			Х
		areas into the drainage design.			

		ВМР	YES	NO	N/A
	12.b.	Overflow parking (parking stalls provided in excess of the County's minimum parking requirements) may be constructed with permeable			х
	12.c.	paving.  Other design concepts that are comparable and equally effective.			Х
13.		ng Area			
	Non-r	etail fuel dispensing areas shall contain the following.			
	13.a.	Overhanging roof structure or canopy. The cover's minimum dimensions must be equal to or greater than the area within the grade break. The cover must not drain onto the fuel dispensing area and the downspouts must be routed to prevent drainage across the fueling area. The fueling area shall drain to the project's treatment control BMP(s) prior to discharging to the storm water conveyance system.	х		
	13.b.	Paved with Portland cement concrete (or equivalent smooth impervious surface). The use of asphalt concrete shall be prohibited.	х		
	13.c.	Have an appropriate slope to prevent ponding, and must be separated from the rest of the site by a grade break that prevents run-on of urban runoff	х		
	13.d.	At a minimum, the concrete fuel dispensing area must extend 6.5 feet (2.0 meters) from the corner of each fuel dispenser, or the length at which the hose and nozzle assembly may be operated plus 1 foot (0.3 meter), whichever is less.	Х		

Please list other project specific Source Control BMPs in the following box. Write <b>N/A</b> if there are none and briefly explain.
are none and orieny explain.

### TREATMENT CONTROL

To select a structural treatment BMP using Treatment Control BMP Selection Matrix (Table 2), each priority project shall compare the list of pollutants for which the downstream receiving waters are impaired (if any), with the pollutants anticipated to be generated by the project (as identified in Table 1). Any pollutants identified by Table 1, which are also causing a Clean Water Act section 303(d) impairment of the receiving waters of the project, shall be considered primary pollutants of concern. Priority projects that are anticipated to generate a primary pollutant of concern shall select a single or combination of stormwater BMPs from Table 2, which **maximizes pollutant removal** for the particular primary pollutant(s) of concern.

Priority projects that are <u>not</u> anticipated to generate a pollutant for which the receiving water is Clean Water Act Section 303(d) impaired shall select a single or combination of stormwater BMPs from Table 2, which are effective for pollutant removal of the identified secondary pollutants of concern, consistent with the "maximum extent practicable" standard.

Table 2. Treatment Control BMP Selection Matrix

Pollutant of Concern	Treatment Control BMP Categories										
	Biofilters	Detention Basins	Infiltration Basins <sup>(2)</sup>	Wet Ponds or Wetlands	Drainage Inserts	Filtration	Hydrodynamic Separator Systems <sup>(3)</sup>				
Sediment	M	Н	Н	Н	L	Н	M				
Nutrients	L	M	M	M	L	M	L				
Heavy Metals	M	М	М	Н	L	Н	L				
Organic Compounds	U	U	U	M	L	М	L				
Trash & Debris	L	Н	U	Н	М	Н	М				
Oxygen Demanding Substances	L	М	М	М	L	М	L				
Bacteria	U	U	Н	Н	L	M	L				
Oil & Grease	M	M	U	U	L	Н	L				
Pesticides	II	U	U	L	L	U	IPs to update this				

<sup>(1)</sup> Copermittees are encouraged to periodically assess the performance characteristics of many of these BMPs to update this table.

- L: Low removal efficiency:
- M: Medium removal efficiency:
- H: High removal efficiency:
- U: Unknown removal efficiency

Sources: Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters (1993), National Stormwater Best Management Practices Database (2001), Guide for BMP Selection in Urban Developed Areas (2001), and Caltrans New Technology Report (2001).

A Treatment BMP must address runoff from developed areas. Please provide the post-construction water quality values for the project. Label outfalls on the BMP map.  $Q_{WQ}$  is dependent on the type of treatment BMP selected for the project.

Tributary Area (acres)	Q <sub>100</sub> (cfs)	QwQ (cfs)
0.25	1.07	0.04
0.22	1.01	0.03
0.04	0.31	0.007
	(acres) 0.25 0.22	(acres)         (cfs)           0.25         1.07           0.22         1.01

Please check the box(s) that best describes the Treatment BMP(s) selected for this project.

# Biofilters ☐ Grass swale ☐ Grass strip ☐ Wetland vegetation swale ☐ Bioretention Detention Basins ☐ Extended/dry detention basi

☐ Extended/dry detention basin with grass lining

☐ Extended/dry detention basin with impervious lining

<sup>(2)</sup> Including trenches and porous pavement.

<sup>(3)</sup> Also known as hydrodynamic devices and baffle boxes.

Infiltration Basins
□ Infiltration basin
☐ Infiltration trench
□ Porous asphalt
□ Porous concrete
□ Porous modular concrete block
Wet Ponds or Wetlands
☐ Wet pond/basin (permanent pool)
☐ Constructed wetland
<b>Drainage Inserts</b> (See note below)
☐ Oil/Water separator
Catch basin insert
☐ Storm drain inserts
☐ Catch basin screens
Filtration
☐ Media filtration
☐ Sand filtration
Hydrodynamic Separator Systems
☐ Swirl Concentrator
☐ Cyclone Separator
☐ Baffle Separator
☐ Gross Solids Removal Device
☐ Linear Radial Device

**Note:** Catch basin inserts and storm drain inserts are excluded from use on County maintained right-of-way and easements.

Include Treatment Datasheet as Attachment E. The datasheet	COMPLETED	NO
should include the following:		
1. Description of how treatment BMP was designed. Provide a	x	
description for each type of treatment BMP.		
2. Engineering calculations for the BMP(s)	х	

Please describe why the selected treatment BMP(s) was selected for this project. For projects utilizing a low performing BMP, please provide a detailed explanation and justification.

Catch basin filter inserts (FloGard™ by Kristar® [or approved equal]) installed on appropriate private drain inlets. The inserts are designed to collect sediment, trash, and debris during low flows (first flush); however, they will not impede peak flows and they help to reduce the hydrocarbons, oil, grease pollutants and metal debris from vehicle brake pads. Insert filters installed on appropriate inlets cleanse the run off per square foot of effective filter area (per manufacturer efficiency specs in Attachment E).

### **MAINTENANCE**

Please check the box that best describes the maintenance mechanism(s) for this project.

CATECODY	SELEC	CTED
CATEGORY	YES	NO
First		
Second		
Third		
Fourth		

Please briefly describe the long-term fiscal resources for the selected maintenance mechanism(s).

The permanent responsability of the post-develoment BMP'S will remain with the owner and/or designated owners or property managament company. A security will be required to back-up maintenance mechanism


### **ATTACHMENTS**

Please include the following attachments.

	ATTACHMENT	COMPLETED	N/A
A	Project Location Map	X	
В	Site Map	X	
C	Relevant Monitoring Data		X
D	Treatment BMP Location Map	X	
Е	Treatment BMP Datasheets		
F	Operation and Maintenance Program for	X	
	Treatment BMPs		
G	Engineer's Certification Sheet	X	

Note: Attachments A and B may be combined.

## ATTACHMENT A LOCATION MAP




# ATTACHMENT B PROJECT SITE MAP







# ATTACHMENT C RELEVANT MONITORING DATA



The Sweetwater River watershed along with the Otay and Pueblo San Diego watersheds combine to form the San Diego Bay watershed area. The Sweetwater River watershed is the largest of the three encompassing 230 of the approximately 415 square mile total. Over 86% of the watershed is within unincorporated jurisdictions. The dominant land uses in the Sweetwater River watershed are urban (29%), open space/ agriculture (22%), and undeveloped (49%). Approximately two-thirds of the land area categorized as urban is composed of residential communities. Approximately 300,000 people



currently reside within the Sweetwater River watershed, and this amount is projected to increase to 365,000 by 2015. The most important watershed issues are related to the protection of municipal water supplies, and the protection and restoration of sensitive wetland and wildlife habitats.

Between the headwaters and the outlet to San Diego Bay, the watershed contains a variety of habitat types including oak and pine woodlands, riparian forest, chaparral, coastal sage scrub, and coastal salt marsh. The upper watershed contains large undeveloped areas within the Cleveland National Forest and Cuyamaca Rancho State Park, the unincorporated communities of Pine Valley, Descanso, and Alpine, and the Viejas Indian Reservation. Unincorporated rural and suburban communities characterize the central part of the watershed. The urbanized lower portion of the Sweetwater watershed contains portions of several cities including San Diego, National City, Chula Vista, La Mesa, and Lemon Grove. Of the cities within the watershed, Chula Vista is the most important in terms of land area.

There are many <u>beneficial water uses within the Sweetwater</u> <u>Watershed</u> as designated in the State Water Resources Control Board's <u>San Diego Region Basin Plan</u>.



project clean water

Leadership, cooperation, and education are the most important tools we have for compelling change.

PCW Webmaster

project clean water

clean water through local commitment and action

### Sweetwater Watershed Beneficial Water Uses

Plan Projects Activities

### Return to Sweetwater Watershed page

Beneficial water uses within the Sweetwater Watershed as designated in the State Water Resources Control Board's <u>San Diego Region Basin Plan</u>.

### Planning Efforts

Home

Overview

Watersheds
San Juan
Santa Margarita
San Luis Rey
Carlsbad
San Dieguito
Penasquitos
San Diego
Pueblo
Sweetwater
Olay
Tijuana
For Kids
Report Dumping
Semi-h

Beneficial Uses	Inland Surface Water	Coastal Waters	Reservoirs and Lakes	Ground Water
Municipal and Domestic Supply	x		x	x
Agricultural Supply	×		x	х
Industrial Service Supply	x	x	x	х
Industrial Process Supply	x		х	
Navigation		×		
Contact Water Recreation	x	х	х	
Non-Contact Water Recreation	х	x	x	
Commercial and Sport Fishing		x		
Biological Habitats of Special Signif.	х	×		
Warm Freshwater Habitat	х		x	
Cold Freshwater Habitat	х		x	
Wildlife Habitat	х	X	X	
Rare, Threatened, or End.	х	×		
Marine Habitat		X		
Migration of Aquatic Organisms		x		
Estuarine Habitat		х		
Shellfish Harvesting		х		

Summary of beneficial use designations.



### Plan Projects Activities



project clean water

Leadership, cooperation, and education are the most important tools we have for compelling change.

PCW Webmaster

-----

# Table 2-5. BENEFICIAL USES OF GROUND WATERS

Ground Water         Hydrologic NM A DIFECTION NUT DIFFER AND DIFFE					BE	BENEFICIAL USE	IAL L	JSE	
DROLOGIC UNIT  HA  HA  B.10  HA  B.20  HA  B.			Hydrologic	Σ	A	-	۵.	ட	<u>ග</u>
HA 8.20 + B.10 + B.20 + B.20 + B.30	Ground water		Unit Racin	>		z	Œ	Œ	≥
HA 8.20 + 8.20 + 8.20 + 9.00  HA 8.20 + 9.00  HA 9.10   0 0   0    HSA 9.12   0 0   0    HSA 9.20   0 0    HA 9.20   0 0    HA 9.20   0 0    HA 10.20   0 0    HA 10.30   0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0 0 0 0 0 0 0 0    HA 10.30   0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			ייים אוור מפאוור	z	Œ	۵	0	တ	Œ
HA 8.10 +			Number				ပ	I	
HA 8.10 + HA 8.10 + HA 8.20 + H 8.20 + HA 9.00  HA 9.10	PUEBLO SAN DIEGO HYDROLOGIC UNI	L	8.00						
HA 2 8.20 + 6 1 10.20 HA 2 8.30 H	Point Loma	HA	8.10						
HA 2 8.30	San Diego Mesa	НА	8.20						
HA 9.00  HSA 9.10  HSA 9.11 0 • 10  HA 9.20 • 0  HA 9.30 • 0  HA 10.00  HA 10.20 • 0  HA 10.20 • 0  HA 10.20 • 0  HA 10.20 • 0	National City		8.30	•					
HA 9.10  HSA 9.11 0 0  HSA 9.12 0 0  HA 9.20 0 0  HA 9.30 0 0  HA 10.00  HA 10.20 + 10.40  HA 11 10.20 + 10.30  HA 11 10.30 0 0	SWEETWATER HYDROLOGIC UNIT		9.00						
HSA 9.11 0 0 HSA 9.12 0 0 HA 9.12 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Lower Sweetwater	НА	9.10		l				
HSA 9.12 HA 9.20 HA 9.30 HA 10.00 HA 11 HA 10.20 HA 11	Telegraph	HSA	9.11	- 1	•	0			
HA 9.20 HA 9.30 HA 10.10 HA 110.20 HA 11 10.20 HA 11 10.20	La Nacion	HSA	9.12	•	•	<u> </u>			
HA 9.30 HA 10.10 HA 10.20 HA 11 10.20 HA 10.20	Middle Sweetwater	НА	9.20	•	•	•			
HA 10.00 HA 10.20 HA 10.20 HA 10.20	Upper Sweetwater	НА	9.30	•	•	_			
Ito     HA     10.10       Itley     HA     10.20       Itley     HA     11.20       HA     10.20	OTAY HYDROLOGIC UNIT		10.00						
illey HA 10.20 (10.20 HA 11.20 HA 10.20 HA 10.30 HA 10.30 HA 10.30	Coronado	HA	10.10						
Illey HA 10.20 10.30 HA 10.30	Otay Valley	НА	10.20	•	•	•			
AH AH	Otay Valley					•	_		
	Dulzura	НА	10.30	•	<u> </u>	•			

- These beneficial uses do not apply westerly of the easterly boundary of the right-of-way of Interstate Highway 5 and this area is excepted from the sources of drinking water policy. The beneficial uses for the remainder of the hydrologic area as shown.
  - 11 This beneficial use designation applies to the portion of Otay HA (10.20), limited to lands within and tributary to Salt Creek on the east and Poggi Canyon on the west and including the several smaller drainage courses between these tributaries of the Otay River.
- Existing Beneficial Use
- O Potential Beneficial Use
- + Excepted From MUN (see text)

# Table 2-2. BENEFICIAL USES OF INLAND SURFACE WATERS

							i			ļ						Γ
							BEN	BENEFICIAL		SE E	Ì	l	l	ŀ	Ì	T
1.2		Σ	⋖	_	۵	ဗ	ı	<u>Դ</u>	æ	œ	ω	>	ပ	<u></u>	~	ഗ
	77 - 1 - 1 - 1 - 1 - 1 - 1 - 1	=	Ü	Z	œ	3	O.	0	ш	ш	_	⋖	0	_	4	۵.
Inland Surface Waters	Hydrologic Unit	Z	2		0	α	S	>	ပ	ပ	0	œ			~	3
	Basin Number				ပ		·I		~	7		Σ	Ω	۵	ш	z
									1		1	1	1		1	T
Sweetwater River Watershed - continued															Ì	
Viejas Creek	9.33	•	•	•	•		-		•	•		•	•	•		
Viejas Creek	9.31	•	•	•	•				•	•		•	•	•		
Loveland Reservoir	9.31					•,	See Reservoirs	eserv	oirs &	Lakes-	s- Table	le 2-4				
Taylor Creek	9.31	•	•	•	•				•	•		•		•		
Japatul Valley	9.32	•	•	•	•				•	•		•		•		
Sweetwater River	9.21	•	•	•	•				•	•	•	•		•	•	
unnamed tributary	9.21	•	•	•	•				•	•	•	•		•	•	
Lawson Creek	9.21	•	•	•	•				•	•		•		•		
Beaver Canyon	9.21	•	•	•	•				•	•		•		•		
Wood Valley	9.21	•	•	•	•				•	•		•		•		
Sycuan Creek	9.25	•	•	•	•				•	•		•		•		
North Fork Sycuan Creek	9.26	•	•	•	•				•	•		•		•		
North Fork Sycuan Creek	9.25	•	•	•	•				•	•		•		•		
Denesa Valley	9.23	•	•	•	•				•	•		•		•		
Harbison Canyon	9.23	•	•	•	•				•	•		•		•		
Galloway Valley	9.24	•	•	•	•				•	•		•		•		
Mexican Canyon	9.21	•	•	•	•				•	•		•		•		
● Cointing Donoficial Use	-	-	1 171	7.7.7.7			1	9		4:	4	seinebariod core due				


Existing Beneficial Use

T Waterbodies are listed multiple times if they cross hydrologic area or sub area boundaries.


O Potential Beneficial Use

 $oldsymbol{2}$  Beneficial use designations apply to all tributaries to the indicated waterbody, if not listed separately.

## ATTACHMENT D TREATMENT BMP LOCATION MAP



## ATTACHMENT E TREATMENT BMP DATASHEET



### **Description and Purpose**

Scheduling is the development of a written plan that includes sequencing of construction activities and the implementation of BMPs such as erosion control and sediment control while taking local climate (rainfall, wind, etc.) into consideration. The purpose is to reduce the amount and duration of soil exposed to erosion by wind, rain, runoff, and vehicle tracking, and to perform the construction activities and control practices in accordance with the planned schedule.

### **Suitable Applications**

Proper sequencing of construction activities to reduce erosion potential should be incorporated into the schedule of every construction project especially during rainy season. Use of other, more costly yet less effective, erosion and sediment control BMPs may often be reduced through proper construction sequencing.

### Limitations

 Environmental constraints such as nesting season prohibitions reduce the full capabilities of this BMP.

### **Implementation**

- Avoid rainy periods. Schedule major grading operations during dry months when practical. Allow enough time before rainfall begins to stabilize the soil with vegetation or physical means or to install sediment trapping devices.
- Plan the project and develop a schedule showing each phase of construction. Clearly show how the rainy season relates to soil

# Objectives EC Erosion Control SE Sediment Control TC Tracking Control WE Wind Erosion Control NS Non-Stormwater Management Control WM Waste Management and Materials Pollution Control Legend:

- ✓ Primary Objective
- ✓ Secondary Objective

### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria
Oil and Grease

**Organics** 

### Potential Alternatives

None



disturbing and re-stabilization activities. Incorporate the construction schedule into the SWPPP.

- Include on the schedule, details on the rainy season implementation and deployment of:
  - Erosion control BMPs
  - Sediment control BMPs
  - Tracking control BMPs
  - Wind erosion control BMPs
  - Non-stormwater BMPs
  - Waste management and materials pollution control BMPs
- Include dates for activities that may require non-stormwater discharges such as dewatering, sawcutting, grinding, drilling, boring, crushing, blasting, painting, hydro-demolition, mortar mixing, pavement cleaning, etc.
- Work out the sequencing and timetable for the start and completion of each item such as site clearing and grubbing, grading, excavation, paving, foundation pouring utilities installation, etc., to minimize the active construction area during the rainy season.
  - Sequence trenching activities so that most open portions are closed before new trenching begins.
  - Incorporate staged seeding and re-vegetation of graded slopes as work progresses.
  - Schedule establishment of permanent vegetation during appropriate planting time for specified vegetation.
- Non-active areas should be stabilized as soon as practical after the cessation of soil disturbing activities or one day prior to the onset of precipitation.
- Monitor the weather forecast for rainfall.
- When rainfall is predicted, adjust the construction schedule to allow the implementation of soil stabilization and sediment treatment controls on all disturbed areas prior to the onset of rain.
- Be prepared year round to deploy erosion control and sediment control BMPs. Erosion may be caused during dry seasons by un-seasonal rainfall, wind, and vehicle tracking. Keep the site stabilized year round, and retain and maintain rainy season sediment trapping devices in operational condition.
- Apply permanent erosion control to areas deemed substantially complete during the project's defined seeding window.

### Costs

Construction scheduling to reduce erosion may increase other construction costs due to reduced economies of scale in performing site grading. The cost effectiveness of scheduling techniques should be compared with the other less effective erosion and sedimentation controls to achieve a cost effective balance.


### **Inspection and Maintenance**

- Verify that work is progressing in accordance with the schedule. If progress deviates, take corrective actions.
- Amend the schedule when changes are warranted.
- Amend the schedule prior to the rainy season to show updated information on the deployment and implementation of construction site BMPs.

#### References

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities Developing Pollution Prevention Plans and Best Management Practices (EPA 832-R-92-005), U.S. Environmental Protection Agency, Office of Water, September 1992.



## **Description and Purpose**

Hydroseeding typically consists of applying a mixture of wood fiber, seed, fertilizer, and stabilizing emulsion with hydromulch equipment, to temporarily protect exposed soils from erosion by water and wind.

### **Suitable Applications**

Hydroseeding is suitable for soil disturbed areas requiring temporary protection until permanent stabilization is established, and disturbed areas that will be re-disturbed following an extended period of inactivity.

#### Limitations

- Hydroseeding may be used alone only when there is sufficient time in the season to ensure adequate vegetation establishment and coverage to provide adequate erosion control. Otherwise, hydroseeding must be used in conjunction with mulching (i.e., straw mulch).
- Steep slopes are difficult to protect with temporary seeding.
- Temporary seeding may not be appropriate in dry periods without supplemental irrigation.
- Temporary vegetation may have to be removed before permanent vegetation is applied.
- Temporary vegetation is not appropriate for short term inactivity.

### Objectives

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater
Management Control

.... Waste Management and

WM Materials Pollution Control

#### Legend:

✓ Primary Objective

√ Secondary Objective

### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

Organics

### Potential Alternatives

EC-3 Hydraulic Mulch

EC-5 Soil Binders

EC-6 Straw Mulch

EC-7 Geotextiles and Mats

EC-8 Wood Mulching



### **Implementation**

In order to select appropriate hydroseeding mixtures, an evaluation of site conditions shall be performed with respect to:

Soil conditions - Maintenance requirements

- Site topography - Sensitive adjacent areas

- Season and climate - Water availability

- Vegetation types - Plans for permanent vegetation

The local office of the U.S.D.A. Natural Resources Conservation Service (NRCS) is an excellent source of information on appropriate seed mixes.

The following steps shall be followed for implementation:

- Avoid use of hydroseeding in areas where the BMP would be incompatible with future earthwork activities and would have to be removed.
- Hydroseeding can be accomplished using a multiple step or one step process. The multiple step process ensures maximum direct contact of the seeds to soil. When the one step process is used to apply the mixture of fiber, seed, etc., the seed rate shall be increased to compensate for all seeds not having direct contact with the soil.
- Prior to application, roughen the area to be seeded with the furrows trending along the contours.
- Apply a straw mulch to keep seeds in place and to moderate soil moisture and temperature until the seeds germinate and grow.
- All seeds shall be in conformance with the California State Seed Law of the Department of Agriculture. Each seed bag shall be delivered to the site sealed and clearly marked as to species, purity, percent germination, dealer's guarantee, and dates of test. The container shall be labeled to clearly reflect the amount of Pure Live Seed (PLS) contained. All legume seed shall be pellet inoculated. Inoculant sources shall be species specific and shall be applied at a rate of 2 lb of inoculant per 100 lb seed.
- Commercial fertilizer shall conform to the requirements of the California Food and Agricultural Code. Fertilizer shall be pelleted or granular form.
- Follow up applications shall be made as needed to cover weak spots and to maintain adequate soil protection.
- Avoid over spray onto roads, sidewalks, drainage channels, existing vegetation, etc.

#### Costs

Average cost for installation and maintenance may vary from as low as \$300 per acre for flat slopes and stable soils, to \$1600 per acre for moderate to steep slopes and/or erosive soils.

	Hydroseeding	Installed Cost per Acre
High Density	Ornamentals	\$400 - \$1600
	Turf Species	\$350
	Bunch Grasses	\$300 - \$1300
Fast Growing	Annual	\$350 - \$650
	Perennial	\$300 - \$800
Non-Competing	Native	\$300 - \$1600
	Non-Native	\$400 - \$500
Sterile	Cereal Grain	\$500

Source: Caltrans Guidance for Soil Stabilization for Temporary Slopes, Nov. 1999


### **Inspection and Maintenance**

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Areas where erosion is evident shall be repaired and BMPs re-applied as soon as possible.
   Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require re-application of BMPs.
- Where seeds fail to germinate, or they germinate and die, the area must be re-seeded, fertilized, and mulched within the planting season, using not less than half the original application rates.
- Irrigation systems, if applicable, should be inspected daily while in use to identify system malfunctions and line breaks. When line breaks are detected, the system must be shut down immediately and breaks repaired before the system is put back into operation.
- Irrigation systems shall be inspected for complete coverage and adjusted as needed to maintain complete coverage.

#### References

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Guidance Document: Soil Stabilization for Temporary Slopes, State of California Department of Transportation (Caltrans), November 1999.



### **Description and Purpose**

Mattings of natural materials are used to cover the soil surface to reduce erosion from rainfall impact, hold soil in place, and absorb and hold moisture near the soil surface. Additionally, matting may be used to stabilize soils until vegetation is established.

### **Suitable Applications**

Mattings are commonly applied on short, steep slopes where erosion hazard is high and vegetation will be slow to establish. Mattings are also used on stream banks where moving water at velocities between 3 ft/s and 6 ft/s are likely to wash out new vegetation, and in areas where the soil surface is disturbed and where existing vegetation has been removed. Matting may also be used when seeding cannot occur (e.g., late season construction and/or the arrival of an early rain season). Erosion control matting should be considered when the soils are fine grained and potentially erosive. These measures should be considered in the following situations.

- Steep slopes, generally steeper than 3:1 (H:V)
- Slopes where the erosion potential is high
- Slopes and disturbed soils where mulch must be anchored
- Disturbed areas where plants are slow to develop
- Channels with flows exceeding 3.3 ft/s

### **Objectives**

EC Erosion Control
SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

✓ Primary Objective

√ Secondary Objective

### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

EC-3 Hydraulic Mulch

EC-4 Hydroseeding

EC-5 Soil Binders

EC-6 Straw Mulch

**EC-8 Wood Mulching** 



- Channels to be vegetated
- Stockpiles
- Slopes adjacent to water bodies of Environmentally Sensitive Areas (ESAs)

#### **Limitations**

- Properly installed mattings provide excellent erosion control but do so at relatively high cost.
   This high cost typically limits the use of mattings to areas of concentrated channel flow and steep slopes.
- Mattings are more costly than other BMP practices, limiting their use to areas where other BMPs are ineffective (e.g. channels, steep slopes).
- Installation is critical and requires experienced contractors. The contractor should install
  the matting material in such a manner that continuous contact between the material and the
  soil occurs.
- Geotextiles and Mats may delay seed germination, due to reduction in soil temperature.
- Blankets and mats are generally not suitable for excessively rocky sites or areas where the final vegetation will be moved (since staples and netting can catch in movers).
- Blankets and mats must be removed and disposed of prior to application of permanent soil stabilization measures.
- Plastic sheeting is easily vandalized, easily torn, photodegradable, and must be disposed of at a landfill.
- Plastic results in 100% runoff, which may cause serious erosion problems in the areas receiving the increased flow.
- The use of plastic should be limited to covering stockpiles or very small graded areas for short periods of time (such as through one imminent storm event) until alternative measures, such as seeding and mulching, may be installed.
- Geotextiles, mats, plastic covers, and erosion control covers have maximum flow rate limitations; consult the manufacturer for proper selection.
- Not suitable for areas that have heavy foot traffic (tripping hazard) e.g., pad areas around buildings under construction.

### **Implementation**

#### **Material Selection**

Organic matting materials have been found to be effective where re-vegetation will be provided by re-seeding. The choice of matting should be based on the size of area, side slopes, surface conditions such as hardness, moisture, weed growth, and availability of materials.

The following natural and synthetic mattings are commonly used:

### Geotextiles

- Material should be a woven polypropylene fabric with minimum thickness of 0.06 in., minimum width of 12 ft and should have minimum tensile strength of 150 lbs (warp), 80 lbs (fill) in conformance with the requirements in ASTM Designation: D 4632. The permittivity of the fabric should be approximately 0.07 sec<sup>-1</sup> in conformance with the requirements in ASTM Designation: D4491. The fabric should have an ultraviolet (UV) stability of 70 percent in conformance with the requirements in ASTM designation: D4355. Geotextile blankets must be secured in place with wire staples or sandbags and by keying into tops of slopes to prevent infiltration of surface waters under geotextile. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Geotextiles may be reused if they are suitable for the use intended.

#### Plastic Covers

- Plastic sheeting should have a minimum thickness of 6 mils, and must be keyed in at the top of slope and firmly held in place with sandbags or other weights placed no more than 10 ft apart. Seams are typically taped or weighted down their entire length, and there should be at least a 12 in. to 24 in. overlap of all seams. Edges should be embedded a minimum of 6 in. in soil.
- All sheeting must be inspected periodically after installation and after significant rainstorms to check for erosion, undermining, and anchorage failure. Any failures must be repaired immediately. If washout or breakages occur, the material should be re-installed after repairing the damage to the slope.

### Erosion Control Blankets/Mats

- Biodegradable rolled erosion control products (RECPs) are typically composed of jute fibers, curled wood fibers, straw, coconut fiber, or a combination of these materials. In order for an RECP to be considered 100% biodegradable, the netting, sewing or adhesive system that holds the biodegradable mulch fibers together must also be biodegradable.
  - Jute is a natural fiber that is made into a yarn that is loosely woven into a biodegradable mesh. It is designed to be used in conjunction with vegetation and has longevity of approximately one year. The material is supplied in rolled strips, which should be secured to the soil with U-shaped staples or stakes in accordance with manufacturers' recommendations.
  - Excelsior (curled wood fiber) blanket material should consist of machine produced mats of curled wood excelsior with 80 percent of the fiber 6 in. or longer. The excelsior blanket should be of consistent thickness. The wood fiber must be evenly distributed over the entire area of the blanket. The top surface of the blanket should be covered with a photodegradable extruded plastic mesh. The blanket should be smolder resistant without the use of chemical additives and should be non-toxic and non-injurious to plant and animal life. Excelsior blankets should be furnished in rolled strips, a minimum of 48 in. wide, and should have an average weight of 0.8 lb/yd², ±10 percent, at the time of manufacture. Excelsior blankets must be secured in place with wire staples. Staples

should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.

- **Straw blanket** should be machine produced mats of straw with a lightweight biodegradable netting top layer. The straw should be attached to the netting with biodegradable thread or glue strips. The straw blanket should be of consistent thickness. The straw should be evenly distributed over the entire area of the blanket. Straw blanket should be furnished in rolled strips a minimum of 6.5 ft wide, a minimum of 80 ft long and a minimum of 0.5 lb/yd². Straw blankets must be secured in place with wire staples. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Wood fiber blanket is composed of biodegradable fiber mulch with extruded plastic netting held together with adhesives. The material is designed to enhance re-vegetation. The material is furnished in rolled strips, which must be secured to the ground with U-shaped staples or stakes in accordance with manufacturers' recommendations.
- Coconut fiber blanket should be a machine produced mat of 100 percent coconut fiber with biodegradable netting on the top and bottom. The coconut fiber should be attached to the netting with biodegradable thread or glue strips. The coconut fiber blanket should be of consistent thickness. The coconut fiber should be evenly distributed over the entire area of the blanket. Coconut fiber blanket should be furnished in rolled strips with a minimum of 6.5 ft wide, a minimum of 80 ft. long and a minimum of 0.5 lb/yd². Coconut fiber blankets must be secured in place with wire staples. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Coconut fiber mesh is a thin permeable membrane made from coconut or corn fiber that is spun into a yarn and woven into a biodegradable mat. It is designed to be used in conjunction with vegetation and typically has longevity of several years. The material is supplied in rolled strips, which must be secured to the soil with U-shaped staples or stakes in accordance with manufacturers' recommendations.
- **Straw coconut fiber blanket** should be machine produced mats of 70 percent straw and 30 percent coconut fiber with a biodegradable netting top layer and a biodegradable bottom net. The straw and coconut fiber should be attached to the netting with biodegradable thread or glue strips. The straw coconut fiber blanket should be of consistent thickness. The straw and coconut fiber should be evenly distributed over the entire area of the blanket. Straw coconut fiber blanket should be furnished in rolled strips a minimum of 6.5 ft wide, a minimum of 80 ft long and a minimum of 0.5 lb/yd². Straw coconut fiber blankets must be secured in place with wire staples. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Non-biodegradable RECPs are typically composed of polypropylene, polyethylene, nylon or other synthetic fibers. In some cases, a combination of biodegradable and synthetic fibers is used to construct the RECP. Netting used to hold these fibers together is typically non-biodegradable as well.

- Plastic netting is a lightweight biaxially oriented netting designed for securing loose mulches like straw or paper to soil surfaces to establish vegetation. The netting is photodegradable. The netting is supplied in rolled strips, which must be secured with Ushaped staples or stakes in accordance with manufacturers' recommendations.
- Plastic mesh is an open weave geotextile that is composed of an extruded synthetic fiber woven into a mesh with an opening size of less than 1/4 in. It is used with revegetation or may be used to secure loose fiber such as straw to the ground. The material is supplied in rolled strips, which must be secured to the soil with U-shaped staples or stakes in accordance with manufacturers' recommendations.
- Synthetic fiber with netting is a mat that is composed of durable synthetic fibers treated to resist chemicals and ultraviolet light. The mat is a dense, three dimensional mesh of synthetic (typically polyolefin) fibers stitched between two polypropylene nets. The mats are designed to be re-vegetated and provide a permanent composite system of soil, roots, and geomatrix. The material is furnished in rolled strips, which must be secured with U-shaped staples or stakes in accordance with manufacturers' recommendations.
- Bonded synthetic fibers consist of a three dimensional geomatrix nylon (or other synthetic) matting. Typically it has more than 90 percent open area, which facilitates root growth. It's tough root reinforcing system anchors vegetation and protects against hydraulic lift and shear forces created by high volume discharges. It can be installed over prepared soil, followed by seeding into the mat. Once vegetated, it becomes an invisible composite system of soil, roots, and geomatrix. The material is furnished in rolled strips that must be secured with U-shaped staples or stakes in accordance with manufacturers' recommendations.
- Combination synthetic and biodegradable RECPs consist of biodegradable fibers, such as wood fiber or coconut fiber, with a heavy polypropylene net stitched to the top and a high strength continuous filament geomatrix or net stitched to the bottom. The material is designed to enhance re-vegetation. The material is furnished in rolled strips, which must be secured with U-shaped staples or stakes in accordance with manufacturers' recommendations.

### Site Preparation

- Proper site preparation is essential to ensure complete contact of the blanket or matting with the soil.
- Grade and shape the area of installation.
- Remove all rocks, clods, vegetation or other obstructions so that the installed blankets or mats will have complete, direct contact with the soil.
- Prepare seedbed by loosening 2 to 3 in. of topsoil.

Seed the area before blanket installation for erosion control and revegetation. Seeding after mat installation is often specified for turf reinforcement application. When seeding prior to blanket

installation, all check slots and other areas disturbed during installation must be re-seeded. Where soil filling is specified, seed the matting and the entire disturbed area after installation and prior to filling the mat with soil.

Fertilize and seed in accordance with seeding specifications or other types of landscaping plans. When using jute matting on a seeded area, apply approximately half the seed before laying the mat and the remainder after laying the mat. The protective matting can be laid over areas where grass has been planted and the seedlings have emerged. Where vines or other ground covers are to be planted, lay the protective matting first and then plant through matting according to design of planting.

#### Check Slots

Check slots are made of glass fiber strips, excelsior matting strips or tight folded jute matting blanket or strips for use on steep, highly erodible watercourses. The check slots are placed in narrow trenches 6 to 12 in. deep across the channel and left flush with the soil surface. They are to cover the full cross section of designed flow.

### Laying and Securing Matting

- Before laying the matting, all check slots should be installed and the friable seedbed made free from clods, rocks, and roots. The surface should be compacted and finished according to the requirements of the manufacturer's recommendations.
- Mechanical or manual lay down equipment should be capable of handling full rolls of fabric and laying the fabric smoothly without wrinkles or folds. The equipment should meet the fabric manufacturer's recommendations or equivalent standards.

### Anchoring

- U-shaped wire staples, metal geotextile stake pins, or triangular wooden stakes can be used to anchor mats and blankets to the ground surface.
- Wire staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Metal stake pins should be 0.188 in. diameter steel with a 1.5 in. steel washer at the head of the pin, and 8 in. in length.
- Wire staples and metal stakes should be driven flush to the soil surface.

### Installation on Slopes

Installation should be in accordance with the manufacturer's recommendations. In general, these will be as follows:

- Begin at the top of the slope and anchor the blanket in a 6 in. deep by 6 in. wide trench. Backfill trench and tamp earth firmly.
- Unroll blanket down slope in the direction of water flow.
- Overlap the edges of adjacent parallel rolls 2 to 3 in. and staple every 3 ft.

- When blankets must be spliced, place blankets end over end (shingle style) with 6 in. overlap. Staple through overlapped area, approximately 12 in. apart.
- Lay blankets loosely and maintain direct contact with the soil. Do not stretch.
- Staple blankets sufficiently to anchor blanket and maintain contact with the soil. Staples should be placed down the center and staggered with the staples placed along the edges. Steep slopes, 1:1 (H:V) to 2:1 (H:V), require a minimum of 2 staples/yd². Moderate slopes, 2:1 (H:V) to 3:1 (H:V), require a minimum of 1 ½ staples/yd².

### Installation in Channels

Installation should be in accordance with the manufacturer's recommendations. In general, these will be as follows:

- Dig initial anchor trench 12 in. deep and 6 in. wide across the channel at the lower end of the project area.
- Excavate intermittent check slots, 6 in. deep and 6 in. wide across the channel at 25 to 30 ft intervals along the channels.
- Cut longitudinal channel anchor trenches 4 in. deep and 4 in. wide along each side of the installation to bury edges of matting, whenever possible extend matting 2 to 3 in. above the crest of the channel side slopes.
- Beginning at the downstream end and in the center of the channel, place the initial end of the first roll in the anchor trench and secure with fastening devices at 12 in. intervals. Note: matting will initially be upside down in anchor trench.
- In the same manner, position adjacent rolls in anchor trench, overlapping the preceding roll a minimum of 3 in.
- Secure these initial ends of mats with anchors at 12 in. intervals, backfill and compact soil.
- Unroll center strip of matting upstream. Stop at next check slot or terminal anchor trench.
   Unroll adjacent mats upstream in similar fashion, maintaining a 3 in. overlap.
- Fold and secure all rolls of matting snugly into all transverse check slots. Lay mat in the bottom of the slot then fold back against itself. Anchor through both layers of mat at 12 in. intervals, then backfill and compact soil. Continue rolling all mat widths upstream to the next check slot or terminal anchor trench.
- Alternate method for non-critical installations: Place two rows of anchors on 6 in. centers at 25 to 30 ft. intervals in lieu of excavated check slots.
- Staple shingled lap spliced ends a minimum of 12 in. apart on 12 in. intervals.
- Place edges of outside mats in previously excavated longitudinal slots; anchor using prescribed staple pattern, backfill, and compact soil.
- Anchor, fill, and compact upstream end of mat in a 12 in. by 6 in. terminal trench.

- Secure mat to ground surface using U-shaped wire staples, geotextile pins, or wooden stakes.
- Seed and fill turf reinforcement matting with soil, if specified.

## Soil Filling (if specified for turf reinforcement)

- Always consult the manufacturer's recommendations for installation.
- Do not drive tracked or heavy equipment over mat.
- Avoid any traffic over matting if loose or wet soil conditions exist.
- Use shovels, rakes, or brooms for fine grading and touch up.
- Smooth out soil filling just exposing top netting of mat.

## Temporary Soil Stabilization Removal

 Temporary soil stabilization removed from the site of the work must be disposed of if necessary.

#### **Costs**

Relatively high compared to other BMPs. Biodegradable materials:  $$0.50 - $0.57/yd^2$ . Permanent materials:  $$3.00 - $4.50/yd^2$ . Staples: \$0.04 - \$0.05/staple. Approximate costs for installed materials are shown below:

Rolled	Erosion Control Products	Installed Cost per Acre
Biodegradable	Jute Mesh	\$6,500
	Curled Wood Fiber	\$10,500
	Straw	\$8,900
	Wood Fiber	\$8,900
	Coconut Fiber	\$13,000
	Coconut Fiber Mesh	\$31,200
	Straw Coconut Fiber	\$10,900
Non-Biodegradable	Plastic Netting	\$2,000
	Plastic Mesh	\$3,200
	Synthetic Fiber with Netting	\$34,800
	Bonded Synthetic Fibers	\$50,000
	Combination with Biodegradable	\$32,000

Source: Caltrans Guidance for Soil Stabilization for Temporary Slopes, Nov. 1999

### Inspection and Maintenance

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season, and at two-week intervals during the non-rainy season.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.

- Areas where erosion is evident shall be repaired and BMPs reapplied as soon as possible.
   Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require reapplication of BMPs.
- If washout or breakage occurs, re-install the material after repairing the damage to the slope or channel.
- Make sure matting is uniformly in contact with the soil.
- Check that all the lap joints are secure.
- Check that staples are flush with the ground.
- Check that disturbed areas are seeded.

#### References

Guides for Erosion and Sediment Controls in California, USDA Soils Conservation Service, January 1991.


National Management Measures to Control Nonpoint Source Pollution from Urban Areas, United States Environmental Protection Agency, 2002.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Guidance Document: Soil Stabilization for Temporary Slopes, State of California Department of Transportation (Caltrans), November 1999

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.


Water Quality Management Plan for The Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.



#### NOTES:

- Slope surface shall be free of rocks, clods, sticks and grass. Mats/blankets shall have good soil contact.
- 2. Lay blankets loosely and stake or staple to maintain direct contact with the soil. Do not stretch.
- 3. Install per manufacturer's recommendations

## TYPICAL INSTALLATION DETAIL




#### NOTES:

- 1. Check slots to be constructed per manufacturers specifications.
- 2. Staking or stapling layout per manufacturers specifications.
- 3. Install per manufacturer's recommendations

## TYPICAL INSTALLATION DETAIL

Silt Fence SE-1



### **Description and Purpose**

A silt fence is made of a filter fabric that has been entrenched, attached to supporting poles, and sometimes backed by a plastic or wire mesh for support. The silt fence detains sediment-laden water, promoting sedimentation behind the fence.

### **Suitable Applications**

Silt fences are suitable for perimeter control, placed below areas where sheet flows discharge from the site. They should also be used as interior controls below disturbed areas where runoff may occur in the form of sheet and rill erosion. Silt fences are generally ineffective in locations where the flow is concentrated and are only applicable for sheet or overland flows. Silt fences are most effective when used in combination with erosion controls. Suitable applications include:

- Along the perimeter of a project.
- Below the toe or down slope of exposed and erodible slopes.
- Along streams and channels.
- Around temporary spoil areas and stockpiles.
- Below other small cleared areas.

#### Limitations

 Do not use in streams, channels, drain inlets, or anywhere flow is concentrated.

### **Objectives**

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

Waste Management and

WM Materials Pollution Control

#### Legend:

✓ Primary Objective

√ Secondary Objective

### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

SE-5 Fiber Rolls

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-9 Straw Bale Barrier



1 of 8

SE-1 Silt Fence

- Do not use in locations where ponded water may cause flooding.
- Do not place fence on a slope, or across any contour line. If not installed at the same elevation throughout, silt fences will create erosion.
- Filter fences will create a temporary sedimentation pond on the upstream side of the fence and may cause temporary flooding. Fences not constructed on a level contour will be overtopped by concentrated flow resulting in failure of the filter fence.
- Improperly installed fences are subject to failure from undercutting, overlapping, or collapsing.
  - Not effective unless trenched and keyed in.
  - Not intended for use as mid-slope protection on slopes greater than 4:1 (H:V).
  - Do not allow water depth to exceed 1.5 ft at any point.

### **Implementation**

#### General

A silt fence is a temporary sediment barrier consisting of filter fabric stretched across and attached to supporting posts, entrenched, and, depending upon the strength of fabric used, supported with plastic or wire mesh fence. Silt fences trap sediment by intercepting and detaining small amounts of sediment-laden runoff from disturbed areas in order to promote sedimentation behind the fence.

Silt fences are preferable to straw bale barriers in many cases. Laboratory work at the Virginia Highway and Transportation Research Council has shown that silt fences can trap a much higher percentage of suspended sediments than can straw bales. While the failure rate of silt fences is lower than that of straw bale barriers, there are many instances where silt fences have been improperly installed. The following layout and installation guidance can improve performance and should be followed:

- Use principally in areas where sheet flow occurs.
- Don't use in streams, channels, or anywhere flow is concentrated. Don't use silt fences to divert flow.
- Don't use below slopes subject to creep, slumping, or landslides.
- Select filter fabric that retains 85% of soil by weight, based on sieve analysis, but that is not finer than an equivalent opening size of 70.
- Install along a level contour, so water does not pond more than 1.5 ft at any point along the silt fence.
- The maximum length of slope draining to any point along the silt fence should be 200 ft or less.
- The maximum slope perpendicular to the fence line should be 1:1.

Silt Fence SE-1

Provide sufficient room for runoff to pond behind the fence and to allow sediment removal equipment to pass between the silt fence and toes of slopes or other obstructions. About 1200 ft<sup>2</sup> of ponding area should be provided for every acre draining to the fence.

- Turn the ends of the filter fence uphill to prevent stormwater from flowing around the fence.
- Leave an undisturbed or stabilized area immediately down slope from the fence where feasible.
- Silt fences should remain in place until the disturbed area is permanently stabilized.

### Design and Layout

Selection of a filter fabric is based on soil conditions at the construction site (which affect the equivalent opening size (EOS) fabric specification) and characteristics of the support fence (which affect the choice of tensile strength). The designer should specify a filter fabric that retains the soil found on the construction site yet that it has openings large enough to permit drainage and prevent clogging. The following criteria is recommended for selection of the equivalent opening size:

- 1. If 50 percent or less of the soil, by weight, will pass the U.S. Standard Sieve No. 200, select the EOS to retain 85 % of the soil. The EOS should not be finer than EOS 70.
- 2. For all other soil types, the EOS should be no larger than the openings in the U.S. Standard Sieve No. 70 except where direct discharge to a stream, lake, or wetland will occur, then the EOS should be no larger than Standard Sieve No. 100.

To reduce the chance of clogging, it is preferable to specify a fabric with openings as large as allowed by the criteria. No fabric should be specified with an EOS smaller than U.S. Standard Sieve No. 100. If 85% or more of a soil, by weight, passes through the openings in a No. 200 sieve, filter fabric should not be used. Most of the particles in such a soil would not be retained if the EOS was too large and they would clog the fabric quickly if the EOS were small enough to capture the soil.

The fence should be supported by a plastic or wire mesh if the fabric selected does not have sufficient strength and bursting strength characteristics for the planned application (as recommended by the fabric manufacturer). Filter fabric material should contain ultraviolet inhibitors and stabilizers to provide a minimum of six months of expected usable construction life at a temperature range of 0 °F to 120 °F.

- Layout in accordance with attached figures.
- For slopes steeper than 2:1 (H:V) and that contain a high number of rocks or large dirt clods that tend to dislodge, it may be necessary to install additional protection immediately adjacent to the bottom of the slope, prior to installing silt fence. Additional protection may be a chain link fence or a cable fence.
- For slopes adjacent to sensitive receiving waters or Environmentally Sensitive Areas (ESAs), silt fence should be used in conjunction with erosion control BMPs.

SE-1 Silt Fence

#### **Materials**

- Silt fence fabric should be woven polypropylene with a minimum width of 36 in. and a minimum tensile strength of 100 lb force. The fabric should conform to the requirements in ASTM designation D4632 and should have an integral reinforcement layer. The reinforcement layer should be a polypropylene, or equivalent, net provided by the manufacturer. The permittivity of the fabric should be between 0.1 sec<sup>-1</sup> and 0.15 sec<sup>-1</sup> in conformance with the requirements in ASTM designation D4491.
- Wood stakes should be commercial quality lumber of the size and shape shown on the plans. Each stake should be free from decay, splits or cracks longer than the thickness of the stake or other defects that would weaken the stakes and cause the stakes to be structurally unsuitable.
- Staples used to fasten the fence fabric to the stakes should be not less than 1.75 in. long and should be fabricated from 15 gauge or heavier wire. The wire used to fasten the tops of the stakes together when joining two sections of fence should be 9 gauge or heavier wire. Galvanizing of the fastening wire will not be required.
- There are new products that may use prefabricated plastic holders for the silt fence and use bar reinforcement instead of wood stakes. If bar reinforcement is used in lieu of wood stakes, use number four or greater bar. Provide end protection for any exposed bar reinforcement.

### **Installation Guidelines**

Silt fences are to be constructed on a level contour. Sufficient area should exist behind the fence for ponding to occur without flooding or overtopping the fence.

- A trench should be excavated approximately 6 in. wide and 6 in. deep along the line the proposed silt fence.
- Bottom of the silt fence should be keyed-in a minimum of 12 in.
- Posts should be spaced a maximum of 6 ft apart and driven securely into the ground a minimum of 18 in. or 12 in. below the bottom of the trench.
- When standard strength filter fabric is used, a plastic or wire mesh support fence should be fastened securely to the upslope side of posts using heavy—duty wire staples at least 1 in. long. The mesh should extend into the trench. When extra-strength filter fabric and closer post spacing are used, the mesh support fence may be eliminated. Filter fabric should be purchased in a long roll, then cut to the length of the barrier. When joints are necessary, filter cloth should be spliced together only at a support post, with a minimum 6 in. overlap and both ends securely fastened to the post.
- The trench should be backfilled with compacted native material.
- Construct silt fences with a setback of at least 3 ft from the toe of a slope. Where a silt fence is determined to be not practicable due to specific site conditions, the silt fence may be constructed at the toe of the slope, but should be constructed as far from the toe of the slope as practicable. Silt fences close to the toe of the slope will be less effective and difficult to maintain.

Silt Fence SE-1

 Construct the length of each reach so that the change in base elevation along the reach does not exceed 1/3 the height of the barrier; in no case should the reach exceed 500 ft.

#### Costs

Average annual cost for installation and maintenance (assumes 6 month useful life): \$7 per lineal foot (\$850 per drainage acre). Range of cost is \$3.50 - \$9.10 per lineal foot.

### **Inspection and Maintenance**

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Repair undercut silt fences.
- Repair or replace split, torn, slumping, or weathered fabric. The lifespan of silt fence fabric is generally 5 to 8 months.
- Silt fences that are damaged and become unsuitable for the intended purpose should be removed from the site of work, disposed of, and replaced with new silt fence barriers.
- Sediment that accumulates in the BMP must be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height. Sediment removed during maintenance may be incorporated into earthwork on the site or disposed at an appropriate location.
- Silt fences should be left in place until the upstream area is permanently stabilized. Until then, the silt fence must be inspected and maintained.
- Holes, depressions, or other ground disturbance caused by the removal of the silt fences should be backfilled and repaired.

#### References

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

National Management Measures to Control Nonpoint Source Pollution from Urban Areas, United States Environmental Protection Agency, 2002.

Proposed Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters, Work Group-Working Paper, USEPA, April 1992.

Sedimentation and Erosion Control Practices, and Inventory of Current Practices (Draft), UESPA, 1990.

Southeastern Wisconsin Regional Planning Commission (SWRPC). Costs of Urban Nonpoint Source Water Pollution Control Measures. Technical Report No. 31. Southeastern Wisconsin Regional Planning Commission, Waukesha, WI. 1991


Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.


SE-1 Silt Fence


Stormwater Management Manual for The Puget Sound Basin, Washington State Department of Ecology, Public Review Draft, 1991.

U.S. Environmental Protection Agency (USEPA). Stormwater Management for Industrial Activities: Developing Pollution Prevention Plans and Best Management Practices. U.S. Environmental Protection Agency, Office of Water, Washington, DC, 1992.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.







SECTION C-C


Stake dimensions are nominal.


The last 8'-0" of fence shall be turned up slope.

- Dimension may vary to fit field condition.
- Stakes shall be spaced at 8'-0" maximum and shall be positioned on downstream side of fence.
- Stakes to overlap and fence fabric to fold around each stake one full turn. Secure fabric to stake with 4 staples.
- Stakes shall be driven tightly together to prevent potential flow-through of sediment at joint. The tops of the stakes shall be secured with wire.
- For end stake, fence fabric shall be folded around two stakes one full turn and secured with 4 staples. ωi
  - Minimum 4 staples per stake. Dimensions shown are typical. 6
- Cross barriers shall be a minimum of 1/3 and a maximum of 1/2 the height of the linear barrier. 10
- Maintenance openings shall be constructed in a manner to ensure sediment remains behind silt fence.
  - Joining sections shall not be placed at sump locations.
- Sandbag rows and layers shall be offset to eliminate gaps.

NOTES

Construct the length of each reach so that the change in base elevation along the reach does not exceed 1/3 the height of the linear barrier, in no case shall the reach length exceed 500.





### **Description and Purpose**

A gravel bag berm is a series of gravel-filled bags placed on a level contour to intercept sheet flows. Gravel bags pond sheet flow runoff, allowing sediment to settle out, and release runoff slowly as sheet flows, preventing erosion.

### **Suitable Applications**

Gravel bag berms may be suitable:

- As a linear sediment control measure:
  - Below the toe of slopes and erodible slopes
  - As sediment traps at culvert/pipe outlets
  - Below other small cleared areas
  - Along the perimeter of a site
  - Down slope of exposed soil areas
  - Around temporary stockpiles and spoil areas
  - Parallel to a roadway to keep sediment off paved areas
  - Along streams and channels
- As linear erosion control measure:

### **Objectives**

SE

EC **Erosion Control** 

Sediment Control

Tracking Control TC

Wind Erosion Control WE

Non-Stormwater Management Control

Waste Management and Materials Pollution Control

### Legend:

**Primary Objective** 

**Secondary Objective** 

### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Roll

SE-8 Sandbag Barrier

SE-9 Straw Bale Barrier



- Along the face and at grade breaks of exposed and erodible slopes to shorten slope length and spread runoff as sheet flow
- At the top of slopes to divert runoff away from disturbed slopes
- As check dams across mildly sloped construction roads

#### Limitations

- Gravel berms may be difficult to remove.
- Removal problems limit their usefulness in landscaped areas.
- Gravel bag berm may not be appropriate for drainage areas greater than 5 acres.
- Runoff will pond upstream of the filter, possibly causing flooding if sufficient space does not exist.
- Degraded gravel bags may rupture when removed, spilling contents.
- Installation can be labor intensive.
- Berms may have limited durability for long-term projects.
- When used to detain concentrated flows, maintenance requirements increase.

### **Implementation**

#### General

A gravel bag berm consists of a row of open graded gravel—filled bags placed on a level contour. When appropriately placed, a gravel bag berm intercepts and slows sheet flow runoff, causing temporary ponding. The temporary ponding provides quiescent conditions allowing sediment to settle. The open graded gravel in the bags is porous, which allows the ponded runoff to flow slowly through the bags, releasing the runoff as sheet flows. Gravel bag berms also interrupt the slope length and thereby reduce erosion by reducing the tendency of sheet flows to concentrate into rivulets, which erode rills, and ultimately gullies, into disturbed, sloped soils. Gravel bag berms are similar to sand bag barriers, but are more porous.

### Design and Layout

- Locate gravel bag berms on level contours.
  - Slopes between 20:1 and 2:1 (H:V): Gravel bags should be placed at a maximum interval of 50 ft (a closer spacing is more effective), with the first row near the slope toe.
  - Slopes 2:1 (H:V) or steeper: Gravel bags should be placed at a maximum interval of 25 ft (a closer spacing is more effective), with the first row placed the slope toe.
- Turn the ends of the gravel bag barriers up slope to prevent runoff from going around the berm.
- Allow sufficient space up slope from the gravel bag berm to allow ponding, and to provide room for sediment storage.

- For installation near the toe of the slope, consider moving the gravel bag barriers away from the slope toe to facilitate cleaning. To prevent flows behind the barrier, bags can be placed perpendicular to a berm to serve as cross barriers.
- Drainage area should not exceed 5 acres.
- In Non-Traffic Areas:
  - Height = 18 in. maximum
  - Top width = 24 in. minimum for three or more layer construction
  - Top width = 12 in. minimum for one or two layer construction
  - Side slopes = 2:1 or flatter
- In Construction Traffic Areas:
  - Height = 12 in. maximum
  - Top width = 24 in. minimum for three or more layer construction.
  - Top width = 12 in. minimum for one or two layer construction.
  - Side slopes = 2:1 or flatter.
- Butt ends of bags tightly
- On multiple row, or multiple layer construction, overlapp butt joints of adjacent row and row beneath.
- Use a pyramid approach when stacking bags.

#### **Materials**

- **Bag Material:** Bags should be woven polypropylene, polyethylene or polyamide fabric or burlap, minimum unit weight of 4 ounces/yd², Mullen burst strength exceeding 300 lb/in² in conformance with the requirements in ASTM designation D3786, and ultraviolet stability exceeding 70% in conformance with the requirements in ASTM designation D4355.
- **Bag Size:** Each gravel-filled bag should have a length of 18 in., width of 12 in., thickness of 3 in., and mass of approximately 33 lbs. Bag dimensions are nominal, and may vary based on locally available materials.
- *Fill Material:* Fill material should be 0.5 to 1 in. Class 2 aggregate base, clean and free from clay, organic matter, and other deleterious material, or other suitable open graded, non-cohesive, porous gravel.

### Costs

Gravel filter: Expensive, since off-site materials, hand construction, and demolition/removal are usually required. Material costs for gravel bags are average of \$2.50 per empty gravel bag. Gravel costs range from \$20-\$35 per yd³.

### **Inspection and Maintenance**


- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Gravel bags exposed to sunlight will need to be replaced every two to three months due to degrading of the bags.
- Reshape or replace gravel bags as needed.
- Repair washouts or other damage as needed.
- Sediment that accumulates in the BMP must be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height. Sediment removed during maintenance may be incorporated into earthwork on the site or disposed at an appropriate location.
- Remove gravel bag berms when no longer needed. Remove sediment accumulation and clean, re-grade, and stabilize the area. Removed sediment should be incorporated in the project or disposed of.

#### References

Handbook of Steel Drainage and Highway Construction, American Iron and Steel Institute, 1983.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Pollution Plan Handbook, First Edition, State of California, Department of Transportation Division of New Technology, Materials and Research, October 1992.



### **Objectives**

EC	Erosion Control	
SE	Sediment Control	1
TC	Tracking Control	
WE	Wind Erosion Control	
NS	Non-Stormwater Management Control	
WM	Waste Management and Materials Pollution Control	

#### Legend:

- ✓ Primary Objective
- ✓ Secondary Objective

### **Description and Purpose**

Storm drain inlet protection consists of a sediment filter or an impounding area around or upstream of a storm drain, drop inlet, or curb inlet. Storm drain inlet protection measures temporarily pond runoff before it enters the storm drain, allowing sediment to settle. Some filter configurations also remove sediment by filtering, but usually the ponding action results in the greatest sediment reduction.

### **Suitable Applications**

Every storm drain inlet receiving sediment-laden runoff should be protected.

#### Limitations

- Drainage area should not exceed 1 acre.
- Straw bales, while potentially effective, have not produced in practice satisfactory results, primarily due to improper installation.
- Requires an adequate area for water to pond without encroaching into portions of the roadway subject to traffic.
- Inlet protection usually requires other methods of temporary protection to prevent sediment-laden stormwater and non-stormwater discharges from entering the storm drain system.
- Sediment removal may be difficult in high flow conditions or if runoff is heavily sediment laden. If high flow conditions are

### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria
Oil and Grease

Organics

### **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Rolls

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-9 Straw Bale Barrier



# SE-10 Storm Drain Inlet Protection

expected, use other onsite sediment trapping techniques in conjunction with inlet protection.

- Frequent maintenance is required.
- For drainage areas larger than 1 acre, runoff should be routed to a sediment-trapping device designed for larger flows. See BMPs SE-2, Sediment Basin, and SE-3, Sediment Traps.
- Excavated drop inlet sediment traps are appropriate where relatively heavy flows are expected, and overflow capability is needed.

### **Implementation**

#### General

Large amounts of sediment may enter the storm drain system when storm drains are installed before the upslope drainage area is stabilized, or where construction is adjacent to an existing storm drain. In cases of extreme sediment loading, the storm drain itself may clog and lose a major portion of its capacity. To avoid these problems, it is necessary to prevent sediment from entering the system at the inlets.

Inlet control measures presented in this handbook should not be used for inlets draining more than one acre. Runoff from larger disturbed areas should be first routed through SE-2, Sediment Basin or SE-3, Sediment Trap. Different types of inlet protection are appropriate for different applications depending on site conditions and the type of inlet. Inlet protection methods not presented in this handbook should be approved by the local stormwater management agency.

### Design and Layout

Identify existing and planned storm drain inlets that have the potential to receive sediment-laden surface runoff. Determine if storm drain inlet protection is needed and which method to use.

- Limit upstream drainage area to 1 acre maximum. For larger drainage areas, use SE-2, Sediment Basin, or SE-3, Sediment Trap, upstream of the inlet protection device.
- The key to successful and safe use of storm drain inlet protection devices is to know where runoff will pond or be diverted.
  - Determine the acceptable location and extent of ponding in the vicinity of the drain inlet. The acceptable location and extent of ponding will influence the type and design of the storm drain inlet protection device.
  - Determine the extent of potential runoff diversion caused by the storm drain inlet protection device. Runoff ponded by inlet protection devices may flow around the device and towards the next downstream inlet. In some cases, this is acceptable; in other cases, serious erosion or downstream property damage can be caused by these diversions. The possibility of runoff diversions will influence whether or not storm drain inlet protection is suitable; and, if suitable, the type and design of the device.
- The location and extent of ponding, and the extent of diversion, can usually be controlled through appropriate placement of the inlet protection device. In some cases, moving the

inlet protection device a short distance upstream of the actual inlet can provide more efficient sediment control, limit ponding to desired areas, and prevent or control diversions.

- Four types of inlet protection are presented below. However, it is recognized that other effective methods and proprietary devices exist and may be selected.
  - Filter Fabric Fence: Appropriate for drainage basins with less than a 5% slope, sheet flows, and flows under 0.5 cfs.
  - Excavated Drop Inlet Sediment Trap: An excavated area around the inlet to trap sediment (SE-3).
  - Gravel bag barrier: Used to create a small sediment trap upstream of inlets on sloped, paved streets. Appropriate for sheet flow or when concentrated flow may exceed 0.5 cfs, and where overtopping is required to prevent flooding.
  - Block and Gravel Filter: Appropriate for flows greater than 0.5 cfs.
- Select the appropriate type of inlet protection and design as referred to or as described in this fact sheet.
- Provide area around the inlet for water to pond without flooding structures and property.
- Grates and spaces around all inlets should be sealed to prevent seepage of sediment-laden water.
- Excavate sediment sumps (where needed) 1 to 2 ft with 2:1 side slopes around the inlet.

#### Installation

- **DI Protection Type 1 Filter Fabric Fence -** The filter fabric fence (Type 1) protection is shown in the attached figure. Similar to constructing a silt fence; see BMP SE-1, Silt Fence. Do not place filter fabric underneath the inlet grate since the collected sediment may fall into the drain inlet when the fabric is removed or replaced.
  - 1. Excavate a trench approximately 6 in. wide and 6 in. deep along the line of the silt fence inlet protection device.
  - 2. Place 2 in. by 2 in. wooden stakes around the perimeter of the inlet a maximum of 3 ft apart and drive them at least 18 in. into the ground or 12 in. below the bottom of the trench. The stakes must be at least 48 in.
  - 3. Lay fabric along bottom of trench, up side of trench, and then up stakes. See SE-1, Silt Fence, for details. The maximum silt fence height around the inlet is 24 in.
  - 4. Staple the filter fabric (for materials and specifications, see SE-1, Silt Fence) to wooden stakes. Use heavy-duty wire staples at least 1 in. in length.
  - 5. Backfill the trench with gravel or compacted earth all the way around.
- *DI Protection Type 2 Excavated Drop Inlet Sediment Trap -* The excavated drop inlet sediment trap (Type 2) is shown in the attached figures. Install filter fabric fence in

accordance with DI Protection Type 1. Size excavated trap to provide a minimum storage capacity calculated at the rate 67 yd3/acre of drainage area.

- DI Protection Type 3 Gravel bag The gravel bag barrier (Type 3) is shown in the figures. Flow from a severe storm should not overtop the curb. In areas of high clay and silts, use filter fabric and gravel as additional filter media. Construct gravel bags in accordance with SE-6, Gravel Bag Berm. Gravel bags should be used due to their high permeability.
  - 1. Use sand bag made of geotextile fabric (not burlap) and fill with 0.75 in. rock or 0.25 in. pea gravel.
  - 2. Construct on gently sloping street.
  - Leave room upstream of barrier for water to pond and sediment to settle.
  - 4. Place several layers of sand bags overlapping the bags and packing them tightly together.
  - 5. Leave gap of one bag on the top row to serve as a spillway. Flow from a severe storm (e.g., 10 year storm) should not overtop the curb.
- DI Protection Type 4 Block and Gravel Filter The block and gravel filter (Type 4) is shown in the figures. Block and gravel filters are suitable for curb inlets commonly used in residential, commercial, and industrial construction.
  - 1. Place hardware cloth or comparable wire mesh with 0.5 in. openings over the drop inlet so that the wire extends a minimum of 1 ft beyond each side of the inlet structure. If more than one strip is necessary, overlap the strips. Place filter fabric over the wire mesh.
  - Place concrete blocks lengthwise on their sides in a single row around the perimeter of the inlet, so that the open ends face outward, not upward. The ends of adjacent blocks should abut. The height of the barrier can be varied, depending on design needs, by stacking combinations of blocks that are 4 in., 8 in., and 12 in. wide. The row of blocks should be at least 12 in. but no greater than 24 in. high.
  - Place wire mesh over the outside vertical face (open end) of the concrete blocks to prevent stone from being washed through the blocks. Use hardware cloth or comparable wire mesh with 0.5 in. opening.
  - 4. Pile washed stone against the wire mesh to the top of the blocks. Use 0.75 to 3 in.

#### Costs

Average annual cost for installation and maintenance (one year useful life) is \$200 per inlet.

## **Inspection and Maintenance**


Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.


- Filter Fabric Fences. If the fabric becomes clogged, torn, or degrades, it should be replaced. Make sure the stakes are securely driven in the ground and are in good shape (i.e., not bent, cracked, or splintered, and are reasonably perpendicular to the ground). Replace damaged stakes.
- Gravel Filters. If the gravel becomes clogged with sediment, it must be carefully removed from the inlet and either cleaned or replaced. Since cleaning gravel at a construction site may be difficult, consider using the sediment-laden stone as fill material and put fresh stone around the inlet. Inspect bags for holes, gashes, and snags, and replace bags as needed. Check gravel bags for proper arrangement and displacement.
- Sediment that accumulates in the BMP must be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height. Sediment removed during maintenance may be incorporated into earthwork on the site ore disposed at an appropriate location.
- Remove storm drain inlet protection once the drainage area is stabilized.
  - Clean and regrade area around the inlet and clean the inside of the storm drain inlet as it must be free of sediment and debris at the time of final inspection.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management Manual for The Puget Sound Basin, Washington State Department of Ecology, Public Review Draft, 1991.







DI PROTECTION TYPE 1
NOT TO SCALE

#### NOTES:


- 1. For use in areas where grading has been completed and final soil stabilization and seeding are pending.
- 2. Not applicable in paved areas.
- 3. Not applicable with concentrated flows.






#### Notes

- 1. For use in cleared and grubbed and in graded areas.
- 2. Shape basin so that longest inflow area faces longest length of trap.
- 3. For concentrated flows, shape basin in 2:1 ratio with length oriented towards direction of flow.



TYPICAL PROTECTION FOR INLET ON SUMP





## TYPICAL PROTECTION FOR INLET ON GRADE

#### NOTES:

- 1. Intended for short-term use.
- 2. Use to inhibit non-storm water flow.
- 3. Allow for proper maintenance and cleanup.
- 4. Bags must be removed after adjacent operation is completed
- 5. Not applicable in areas with high silts and clays without filter fabric.


DI PROTECTION TYPE 3 NOT TO SCALE





DI PROTECTION - TYPE 4

NOT TO SCALE



# Objectives EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater
Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

✓ Primary Objective

/ Secondary Objective

#### **Description and Purpose**

A stabilized construction access is defined by a point of entrance/exit to a construction site that is stabilized to reduce the tracking of mud and dirt onto public roads by construction vehicles.

#### **Suitable Applications**

Use at construction sites:

- Where dirt or mud can be tracked onto public roads.
- Adjacent to water bodies.
- Where poor soils are encountered.
- Where dust is a problem during dry weather conditions.

#### **Limitations**

- Entrances and exits require periodic top dressing with additional stones.
- This BMP should be used in conjunction with street sweeping on adjacent public right of way.
- Entrances and exits should be constructed on level ground only.
- Stabilized construction entrances are rather expensive to construct and when a wash rack is included, a sediment trap of some kind must also be provided to collect wash water runoff.

#### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria
Oil and Grease

Organics

#### Potential Alternatives



#### **Implementation**

#### General

A stabilized construction entrance is a pad of aggregate underlain with filter cloth located at any point where traffic will be entering or leaving a construction site to or from a public right of way, street, alley, sidewalk, or parking area. The purpose of a stabilized construction entrance is to reduce or eliminate the tracking of sediment onto public rights of way or streets. Reducing tracking of sediments and other pollutants onto paved roads helps prevent deposition of sediments into local storm drains and production of airborne dust.

Where traffic will be entering or leaving the construction site, a stabilized construction entrance should be used. NPDES permits require that appropriate measures be implemented to prevent tracking of sediments onto paved roadways, where a significant source of sediments is derived from mud and dirt carried out from unpaved roads and construction sites.

Stabilized construction entrances are moderately effective in removing sediment from equipment leaving a construction site. The entrance should be built on level ground. Advantages of the Stabilized Construction Entrance/Exit is that it does remove some sediment from equipment and serves to channel construction traffic in and out of the site at specified locations. Efficiency is greatly increased when a washing rack is included as part of a stabilized construction entrance/exit.

#### Design and Layout

- Construct on level ground where possible.
- Select 3 to 6 in. diameter stones.
- Use minimum depth of stones of 12 in. or as recommended by soils engineer.
- Construct length of 50 ft minimum, and 30 ft minimum width.
- Rumble racks constructed of steel panels with ridges and installed in the stabilized entrance/exit will help remove additional sediment and to keep adjacent streets clean.
- Provide ample turning radii as part of the entrance.
- Limit the points of entrance/exit to the construction site.
- Limit speed of vehicles to control dust.
- Properly grade each construction entrance/exit to prevent runoff from leaving the construction site.
- Route runoff from stabilized entrances/exits through a sediment trapping device before discharge.
- Design stabilized entrance/exit to support heaviest vehicles and equipment that will use it.
- Select construction access stabilization (aggregate, asphaltic concrete, concrete) based on longevity, required performance, and site conditions. Do not use asphalt concrete (AC) grindings for stabilized construction access/roadway.

- If aggregate is selected, place crushed aggregate over geotextile fabric to at least 12 in. depth, or place aggregate to a depth recommended by a geotechnical engineer. A crushed aggregate greater than 3 in. but smaller than 6 in. should be used.
- Designate combination or single purpose entrances and exits to the construction site.
- Require that all employees, subcontractors, and suppliers utilize the stabilized construction access.
- Implement SE-7, Street Sweeping and Vacuuming, as needed.
- All exit locations intended to be used for more than a two-week period should have stabilized construction entrance/exit BMPs.

#### **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMPs are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect local roads adjacent to the site daily. Sweep or vacuum to remove visible accumulated sediment.
- Remove aggregate, separate and dispose of sediment if construction entrance/exit is clogged with sediment.
- Keep all temporary roadway ditches clear.
- Check for damage and repair as needed.
- Replace gravel material when surface voids are visible.
- Remove all sediment deposited on paved roadways within 24 hours.
- Remove gravel and filter fabric at completion of construction

#### Costs

Average annual cost for installation and maintenance may vary from \$1,200 to \$4,800 each, averaging \$2,400 per entrance. Costs will increase with addition of washing rack, and sediment trap. With wash rack, costs range from \$1,200 - \$6,000 each, averaging \$3,600 per entrance.

#### References

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

National Management Measures to Control Nonpoint Source Pollution from Urban Areas, USEPA Agency, 2002.

Proposed Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters, Work Group Working Paper, USEPA, April 1992.


Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.


Virginia Erosion and Sedimentation Control Handbook, Virginia Department of Conservation and Recreation, Division of Soil and Water Conservation, 1991.


Guidance Specifying Management Measures for Nonpoint Pollution in Coastal Waters, EPA 840-B-9-002, USEPA, Office of Water, Washington, DC, 1993.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.




# SECTION B-B







## SECTION B-B



#### SECTION A-A NOT TO SCALE





-		
EC	Erosion Control	1
SE	Sediment Control	✓
TC	Tracking Control	
WE	Wind Erosion Control	

NS Non-Stormwater
Management Control
Waste Management and

Materials Pollution Control

#### Legend:

**Objectives** 

- ✔ Primary Objective
- √ Secondary Objective

## **Description and Purpose**

Water conservation practices are activities that use water during the construction of a project in a manner that avoids causing erosion and the transport of pollutants offsite. These practices can reduce or eliminate non-stormwater discharges.

#### **Suitable Applications**

Water conservation practices are suitable for all construction sites where water is used, including piped water, metered water, trucked water, and water from a reservoir.

#### Limitations

None identified.

#### **Implementation**

- Keep water equipment in good working condition.
- Stabilize water truck filling area.
- Repair water leaks promptly.
- Washing of vehicles and equipment on the construction site is discouraged.
- Avoid using water to clean construction areas. If water must be used for cleaning or surface preparation, surface should be swept and vacuumed first to remove dirt. This will minimize amount of water required.

#### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals Bacteria

Oil and Grease

**Organics** 

#### **Potential Alternatives**



# NS-1 Water Conservation Practices

- Direct construction water runoff to areas where it can soak into the ground or be collected and reused.
- Authorized non-stormwater discharges to the storm drain system, channels, or receiving waters are acceptable with the implementation of appropriate BMPs.
- Lock water tank valves to prevent unauthorized use.

#### Costs


The cost is small to none compared to the benefits of conserving water.

## **Inspection and Maintenance**

- Inspect and verify that activity based BMPs are in place prior to the commencement of authorized non-stormwater discharges.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges are occurring.
- Repair water equipment as needed to prevent unintended discharges.
  - Water trucks
  - Water reservoirs (water buffalos)
  - Irrigation systems
  - Hydrant connections

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.



#### Objectives

_		
EC	Erosion Control	
SE	Sediment Control	
TC	Tracking Control	
WE	Wind Erosion Control	
NS	Non-Stormwater Management Control	✓
WM	Waste Management and Materials Pollution Control	✓

#### Legend:

- **✓** Primary Objective
- √ Secondary Objective

#### **Description and Purpose**

Concrete curing is used in the construction of structures such as bridges, retaining walls, pump houses, large slabs, and structured foundations. Concrete curing includes the use of both chemical and water methods. Discharges of stormwater and non-stormwater exposed to concrete during curing may have a high pH and may contain chemicals, metals, and fines. Proper procedures reduce or eliminate the contamination of stormwater runoff during concrete curing.

## **Suitable Applications**

Suitable applications include all projects where Portland Cement Concrete (PCC) and concrete curing chemicals are placed where they can be exposed to rainfall, runoff from other areas, or where runoff from the PCC will leave the site.

#### Limitations

None identified.

## **Implementation**

#### **Chemical Curing**

- Avoid over spray of curing compounds.
- Minimize the drift of chemical cure as much as possible by applying the curing compound close to the concrete surface. Apply an amount of compound that covers the surface, but does not allow any runoff of the compound.
- Use proper storage and handling techniques for concrete curing compounds. Refer to WM-1, Material Delivery and Storage.

# Targeted Constituents Sediment

Nutrients
Trash
Metals
Bacteria
Oil and Grease
Organics

#### **Potential Alternatives**



- Protect drain inlets prior to the application of curing compounds.
- Refer to WM-4, Spill Prevention and Control.

## Water Curing for Bridge Decks, Retaining Walls, and other Structures

- Direct cure water away from inlets and watercourses to collection areas for infiltration or other means of removal in accordance with all applicable permits.
- Collect cure water at the top of slopes and transport or dispose of water in a non-erodible manner. See EC-9 Earth Dikes and Drainage Swales, EC-10, Velocity Dissipation Devices, and EC-11, Slope Drains.
- Utilize wet blankets or a similar method that maintains moisture while minimizing the use and possible discharge of water.

#### Costs

All of the above measures are generally low cost.

## **Inspection and Maintenance**


- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Ensure that employees and subcontractors implement appropriate measures for storage, handling, and use of curing compounds.
- Inspect cure containers and spraying equipment for leaks.

#### References

Blue Print for a Clean Bay-Construction-Related Industries: Best Management Practices for Stormwater Pollution Prevention; Santa Clara Valley Non Point Source Pollution Control Program, 1992.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



## Objectives

EC	Erosion Control	
SE	Sediment Control	
TC	Tracking Control	
WE	Wind Erosion Control	
NS	Non-Stormwater Management Control	✓
WM	Waste Management and Materials Pollution Control	✓

#### Legend:

- ✓ Primary Objective
- ✓ Secondary Objective

## **Description and Purpose**

Concrete finishing methods are used for bridge deck rehabilitation, paint removal, curing compound removal, and final surface finish appearances. Methods include sand blasting, shot blasting, grinding, or high pressure water blasting. Stormwater and non-stormwater exposed to concrete finishing by-products may have a high pH and may contain chemicals, metals, and fines. Proper procedures and implementation of appropriate BMPs can minimize the impact that concrete-finishing methods may have on stormwater and non-stormwater discharges.

## **Suitable Applications**

These procedures apply to all construction locations where concrete finishing operations are performed.

#### Limitations

None identified.

#### **Implementation**

- Collect and properly dispose of water from high-pressure water blasting operations.
- Collect contaminated water from blasting operations at the top of slopes. Transport or dispose of contaminated water while using BMPs such as those for erosion control. Refer to EC-9, Earth Dikes and Drainage Swales, EC-10, Velocity Dissipation Devices, and EC-11, Slope Drains.

#### **Targeted Constituents**

	raigeted constituents	
•	Sediment	1
	Nutrients	
	Trash	
	Metals	✓
	Bacteria	
	Oil and Grease	_
	Organics	<b>√</b>

#### **Potential Alternatives**



- Direct water from blasting operations away from inlets and watercourses to collection areas for infiltration or other means of removal (dewatering). Refer to NS-2 De-Watering Operations.
- Protect inlets during sandblasting operations. Refer to SE-10, Storm Drain Inlet Protection.
- Refer to WM-8, Concrete Waste Management for disposal of concrete based debris.
- Minimize the drift of dust and blast material as much as possible by keeping the blasting nozzle close to the surface.
- When blast residue contains a potentially hazardous waste, refer to WM-6, Hazardous Waste Management.

#### Costs

These measures are generally of low cost.

#### **Inspection and Maintenance**


- Inspect and verify that activity-based BMPs are in place prior to the commencement of
  associated activities. While activities associated with the BMP are under way, inspect weekly
  during the rainy season and at two-week intervals in the non-rainy season to verify
  continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Sweep or vacuum up debris from sandblasting at the end of each shift.
- At the end of each work shift, remove and contain liquid and solid waste from containment structures, if any, and from the general work area.

#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



#### Objectives

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

✓ Primary Objective

✓ Secondary Objective

#### **Description and Purpose**

Prevent, reduce, or eliminate the discharge of pollutants from material delivery and storage to the stormwater system or watercourses by minimizing the storage of hazardous materials onsite, storing materials in a designated area, installing secondary containment, conducting regular inspections, and training employees and subcontractors.

This best management practice covers only material delivery and storage. For other information on materials, see WM-2, Material Use, or WM-4, Spill Prevention and Control. For information on wastes, see the waste management BMPs in this section.

#### **Suitable Applications**

These procedures are suitable for use at all construction sites with delivery and storage of the following materials:

- Soil stabilizers and binders
- Pesticides and herbicides
- Fertilizers
- Detergents
- Plaster
- Petroleum products such as fuel, oil, and grease
- Asphalt and concrete components

#### **Targeted Constituents**

Se	ediment	✓
N	utrients	✓
Tr	ash	✓
М	etals	✓
Ва	acteria	
0	il and Grease	✓
0	rganics	<b>√</b>

#### **Potential Alternatives**



# WM-1 Material Delivery and Storage

- Hazardous chemicals such as acids, lime, glues, adhesives, paints, solvents, and curing compounds
- Concrete compounds
- Other materials that may be detrimental if released to the environment

#### Limitations

- Space limitation may preclude indoor storage.
- Storage sheds often must meet building and fire code requirements.

#### **Implementation**

The following steps should be taken to minimize risk:

- Temporary storage area should be located away from vehicular traffic.
- Material Safety Data Sheets (MSDS) should be supplied for all materials stored.
- Construction site areas should be designated for material delivery and storage.
- Material delivery and storage areas should be located near the construction entrances, away from waterways, if possible.
  - Avoid transport near drainage paths or waterways.
  - Surround with earth berms. See EC-9, Earth Dikes and Drainage Swales.
  - Place in an area which will be paved.
- Storage of reactive, ignitable, or flammable liquids must comply with the fire codes of your area. Contact the local Fire Marshal to review site materials, quantities, and proposed storage area to determine specific requirements. See the Flammable and Combustible Liquid Code, NFPA30.
- An up to date inventory of materials delivered and stored onsite should be kept.
- Hazardous materials storage onsite should be minimized.
- Hazardous materials should be handled as infrequently as possible.
- During the rainy season, consider storing materials in a covered area. Store materials in secondary containments such as earthen dike, horse trough, or even a children's wading pool for non-reactive materials such as detergents, oil, grease, and paints. Small amounts of material may be secondarily contained in "bus boy" trays or concrete mixing trays.
- Do not store chemicals, drums, or bagged materials directly on the ground. Place these items on a pallet and, when possible, in secondary containment.

- If drums must be kept uncovered, store them at a slight angle to reduce ponding of rainwater on the lids to reduce corrosion. Domed plastic covers are inexpensive and snap to the top of drums, preventing water from collecting.
- Chemicals should be kept in their original labeled containers.
- Employees and subcontractors should be trained on the proper material delivery and storage practices.
- Employees trained in emergency spill cleanup procedures must be present when dangerous materials or liquid chemicals are unloaded.
- If significant residual materials remain on the ground after construction is complete, properly remove materials and any contaminated soil. See WM-7, Contaminated Soil Management. If the area is to be paved, pave as soon as materials are removed to stabilize the soil.

## **Material Storage Areas and Practices**

- Liquids, petroleum products, and substances listed in 40 CFR Parts 110, 117, or 302 should be stored in approved containers and drums and should not be overfilled. Containers and drums should be placed in temporary containment facilities for storage.
- A temporary containment facility should provide for a spill containment volume able to contain precipitation from a 25 year storm event, plus the greater of 10% of the aggregate volume of all containers or 100% of the capacity of the largest container within its boundary, whichever is greater.
- A temporary containment facility should be impervious to the materials stored therein for a minimum contact time of 72 hours.
- A temporary containment facility should be maintained free of accumulated rainwater and spills. In the event of spills or leaks, accumulated rainwater and spills should be collected and placed into drums. These liquids should be handled as a hazardous waste unless testing determines them to be non-hazardous. All collected liquids or non-hazardous liquids should be sent to an approved disposal site.
- Sufficient separation should be provided between stored containers to allow for spill cleanup and emergency response access.
- Incompatible materials, such as chlorine and ammonia, should not be stored in the same temporary containment facility.
- Throughout the rainy season, each temporary containment facility should be covered during non-working days, prior to, and during rain events.
- Materials should be stored in their original containers and the original product labels should be maintained in place in a legible condition. Damaged or otherwise illegible labels should be replaced immediately.

# WM-1 Material Delivery and Storage

- Bagged and boxed materials should be stored on pallets and should not be allowed to accumulate on the ground. To provide protection from wind and rain throughout the rainy season, bagged and boxed materials should be covered during non-working days and prior to and during rain events.
- Stockpiles should be protected in accordance with WM-3, Stockpile Management.
- Materials should be stored indoors within existing structures or sheds when available.
- Proper storage instructions should be posted at all times in an open and conspicuous location.
- An ample supply of appropriate spill clean up material should be kept near storage areas.
- Also see WM-6, Hazardous Waste Management, for storing of hazardous materials.

#### **Material Delivery Practices**

- Keep an accurate, up-to-date inventory of material delivered and stored onsite.
- Arrange for employees trained in emergency spill cleanup procedures to be present when dangerous materials or liquid chemicals are unloaded.

#### Spill Cleanup

- Contain and clean up any spill immediately.
- Properly remove and dispose of any hazardous materials or contaminated soil if significant residual materials remain on the ground after construction is complete. See WM-7, Contaminated Soil Management.
- See WM-4, Spill Prevention and Control, for spills of chemicals and/or hazardous materials.

#### Cost

 The largest cost of implementation may be in the construction of a materials storage area that is covered and provides secondary containment.

## **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Keep an ample supply of spill cleanup materials near the storage area.
- Keep storage areas clean, well organized, and equipped with ample cleanup supplies as appropriate for the materials being stored.
- Repair or replace perimeter controls, containment structures, covers, and liners as needed to maintain proper function.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Coastal Nonpoint Pollution Control Program: Program Development and Approval Guidance, Working Group Working Paper; USEPA, April 1992.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.



#### **Description and Purpose**

Prevent or reduce the discharge of pollutants to drainage systems or watercourses from leaks and spills by reducing the chance for spills, stopping the source of spills, containing and cleaning up spills, properly disposing of spill materials, and training employees.

This best management practice covers only spill prevention and control. However, WM-1, Materials Delivery and Storage, and WM-2, Material Use, also contain useful information, particularly on spill prevention. For information on wastes, see the waste management BMPs in this section.

#### **Suitable Applications**

This BMP is suitable for all construction projects. Spill control procedures are implemented anytime chemicals or hazardous substances are stored on the construction site, including the following materials:

- Soil stabilizers/binders
- Dust palliatives
- Herbicides
- Growth inhibitors
- Fertilizers
- Deicing/anti-icing chemicals

#### Objectives

EC	Erosion Control	
SE	Sediment Control	
TC	Tracking Control	
WE	Wind Erosion Control	
NS	Non-Stormwater	
140	Management Control	
WM	Waste Management and	1
• • • • • • • • • • • • • • • • • • • •	Materials Pollution Control	

#### Legend:

- **✓** Primary Objective
- ✓ Secondary Objective

#### **Targeted Constituents**

_	
Sediment	✓
Nutrients	✓
Trash	✓
Metals	✓
Bacteria	
Oil and Grease	✓
Organics	✓

#### **Potential Alternatives**



- Fuels
- Lubricants
- Other petroleum distillates

#### **Limitations**

- In some cases it may be necessary to use a private spill cleanup company.
- This BMP applies to spills caused by the contractor and subcontractors.
- Procedures and practices presented in this BMP are general. Contractor should identify appropriate practices for the specific materials used or stored onsite

#### **Implementation**

The following steps will help reduce the stormwater impacts of leaks and spills:

#### **Education**

- Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills.
- Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
- Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- Establish a continuing education program to indoctrinate new employees.
- Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.

#### General Measures

- To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- Store hazardous materials and wastes in covered containers and protect from vandalism.
- Place a stockpile of spill cleanup materials where it will be readily accessible.
- Train employees in spill prevention and cleanup.
- Designate responsible individuals to oversee and enforce control measures.
- Spills should be covered and protected from stormwater runon during rainfall to the extent that it doesn't compromise clean up activities.
- Do not bury or wash spills with water.

- Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with WM-10, Liquid Waste Management.
- Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- Place proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- Keep waste storage areas clean, well organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

#### Cleanup

- Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be sent to either a certified laundry (rags) or disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

#### **Minor Spills**

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
  - Contain the spread of the spill.
  - Recover spilled materials.
  - Clean the contaminated area and properly dispose of contaminated materials.

## Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

- Spills should be cleaned up immediately:
  - Contain spread of the spill.
  - Notify the project foreman immediately.
  - If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
  - If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
  - If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

#### Significant/Hazardous Spills

- For significant or hazardous spills that cannot be controlled by personnel in the immediate vicinity, the following steps should be taken:
  - Notify the local emergency response by dialing 911. In addition to 911, the contractor will notify the proper county officials. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
  - Notify the Governor's Office of Emergency Services Warning Center, (916) 845-8911.
  - For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
  - Notification should first be made by telephone and followed up with a written report.
  - The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
  - Other agencies which may need to be consulted include, but are not limited to, the Fire Department, the Public Works Department, the Coast Guard, the Highway Patrol, the City/County Police Department, Department of Toxic Substances, California Division of Oil and Gas, Cal/OSHA, etc.

#### Reporting<sup>\*</sup>

- Report significant spills to local agencies, such as the Fire Department; they can assist in cleanup.
- Federal regulations require that any significant oil spill into a water body or onto an adjoining shoreline be reported to the National Response Center (NRC) at 800-424-8802 (24 hours).

Use the following measures related to specific activities:

### Vehicle and Equipment Maintenance

- If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- Regularly inspect onsite vehicles and equipment for leaks and repair immediately
- Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- Place drip pans or absorbent materials under paving equipment when not in use.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
   Remove the absorbent materials promptly and dispose of properly.
- Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip
  pans or other open containers lying around
- Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place
  the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal.
  Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
- Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

#### Vehicle and Equipment Fueling

- If fueling must occur onsite, use designate areas, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- Discourage "topping off" of fuel tanks.
- Always use secondary containment, such as a drain pan, when fueling to catch spills/ leaks.

#### Costs

Prevention of leaks and spills is inexpensive. Treatment and/ or disposal of contaminated soil or water can be quite expensive.

## **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur.

5 of 6

# **Spill Prevention and Control**


- Keep ample supplies of spill control and cleanup materials onsite, near storage, unloading, and maintenance areas.
- Update your spill prevention and control plan and stock cleanup materials as changes occur
  in the types of chemicals onsite.

#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.



# Materials Pollution Control Legend:

**Objectives** 

EC

SE

TC

WE

NS

**Erosion Control** 

Sediment Control

**Tracking Control** 

Wind Erosion Control Non-Stormwater

Management Control
Waste Management and

**✓** Primary Objective

/ Secondary Objective

#### **Description and Purpose**

Prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employee and subcontractors.

#### **Suitable Applications**

Concrete waste management procedures and practices are implemented on construction projects where:

- Concrete is used as a construction material or where concrete dust and debris result form demolition activities
- Slurries containing portland cement concrete (PCC) or asphalt concrete (AC) are generated, such as from saw cutting, coring, grinding, grooving, and hydro-concrete demolition
- Concrete trucks and other concrete-coated equipment are washed onsite
- Mortar-mixing stations exist
- See also NS-8, Vehicle and Equipment Cleaning

#### **Limitations**

Offsite washout of concrete wastes may not always be possible.

# Sediment Nutrients Trash Metals Bacteria Oil and Grease Organics

**Targeted Constituents** 

#### **Potential Alternatives**



# VM-8 Concrete Waste Management

#### **Implementation**

The following steps will help reduce stormwater pollution from concrete wastes:

- Discuss the concrete management techniques described in this BMP (such as handling of concrete waste and washout) with the ready-mix concrete supplier before any deliveries are made.
- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- Store dry and wet materials under cover, away from drainage areas.
- Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks offsite or in designated areas only.
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.
- For onsite washout:
  - Locate washout area at least 50 feet from storm drains, open ditches, or water bodies.
     Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
  - Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly.
- Avoid creating runoff by draining water to a bermed or level area when washing concrete to remove fine particles and expose the aggregate.
- Do not wash sweepings from exposed aggregate concrete into the street or storm drain.
   Collect and return sweepings to aggregate base stockpile or dispose in the trash.

#### **Education**

- Educate employees, subcontractors, and suppliers on the concrete waste management techniques described herein.
- Arrange for contractor's superintendent or representative to oversee and enforce concrete waste management procedures.

#### Concrete Slurry Wastes

- PCC and AC waste should not be allowed to enter storm drains or watercourses.
- PCC and AC waste should be collected and disposed of or placed in a temporary concrete washout facility.
- A sign should be installed adjacent to each temporary concrete washout facility to inform concrete equipment operators to utilize the proper facilities.

- Below grade concrete washout facilities are typical. Above grade facilities are used if excavation is not practical.
- A foreman or construction supervisor should monitor onsite concrete working tasks, such as saw cutting, coring, grinding and grooving to ensure proper methods are implemented.
- Saw-cut PCC slurry should not be allowed to enter storm drains or watercourses. Residue from grinding operations should be picked up by means of a vacuum attachment to the grinding machine. Saw cutting residue should not be allowed to flow across the pavement and should not be left on the surface of the pavement. See also NS-3, Paving and Grinding Operations; and WM-10, Liquid Waste Management.
- Slurry residue should be vacuumed and disposed in a temporary pit (as described in OnSite Temporary Concrete Washout Facility, Concrete Transit Truck Washout Procedures, below) and allowed to dry. Dispose of dry slurry residue in accordance with WM-5, Solid Waste Management.

## Onsite Temporary Concrete Washout Facility, Transit Truck Washout Procedures

- Temporary concrete washout facilities should be located a minimum of 50 ft from storm drain inlets, open drainage facilities, and watercourses. Each facility should be located away from construction traffic or access areas to prevent disturbance or tracking.
- A sign should be installed adjacent to each washout facility to inform concrete equipment operators to utilize the proper facilities.
- Temporary concrete washout facilities should be constructed above grade or below grade at the option of the contractor. Temporary concrete washout facilities should be constructed and maintained in sufficient quantity and size to contain all liquid and concrete waste generated by washout operations.
- Temporary washout facilities should have a temporary pit or bermed areas of sufficient volume to completely contain all liquid and waste concrete materials generated during washout procedures.
- Washout of concrete trucks should be performed in designated areas only.
- Only concrete from mixer truck chutes should be washed into concrete wash out.
- Concrete washout from concrete pumper bins can be washed into concrete pumper trucks and discharged into designated washout area or properly disposed of offsite.
- Once concrete wastes are washed into the designated area and allowed to harden, the concrete should be broken up, removed, and disposed of per WM-5, Solid Waste Management. Dispose of hardened concrete on a regular basis.
- Temporary Concrete Washout Facility (Type Above Grade)
  - Temporary concrete washout facility (type above grade) should be constructed as shown on the details at the end of this BMP, with a recommended minimum length and

# WM-8 Concrete Waste Management

minimum width of 10 ft, but with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations.

- Straw bales, wood stakes, and sandbag materials should conform to the provisions in SE-9, Straw Bale Barrier.
- Plastic lining material should be a minimum of 10 mil in polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.
- Temporary Concrete Washout Facility (Type Below Grade)
  - Temporary concrete washout facilities (type below grade) should be constructed as shown on the details at the end of this BMP, with a recommended minimum length and minimum width of 10 ft. The quantity and volume should be sufficient to contain all liquid and concrete waste generated by washout operations.
  - Lath and flagging should be commercial type.
  - Plastic lining material should be a minimum of 10 mil polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.

## Removal of Temporary Concrete Washout Facilities

- When temporary concrete washout facilities are no longer required for the work, the hardened concrete should be removed and disposed of. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and disposed of.
- Holes, depressions or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired.

#### Costs

All of the above are low cost measures.

## **Inspection and Maintenance**


- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Temporary concrete washout facilities should be maintained to provide adequate holding capacity with a minimum freeboard of 4 in. for above grade facilities and 12 in. for below grade facilities. Maintaining temporary concrete washout facilities should include removing and disposing of hardened concrete and returning the facilities to a functional condition. Hardened concrete materials should be removed and disposed of.
- Washout facilities must be cleaned, or new facilities must be constructed and ready for use once the washout is 75% full.


#### References


Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.









#### NOTES


- 1. ACTUAL LAYOUT DETERMINED IN FIELD.
- 2. THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 30 FT. OF THE TEMPORARY CONCRETE WASHOUT FACILITY.





7 of 7

# Sanitary/Septic Waste Management WM-9



#### Objectives

EC	Erosion Control	
SE	Sediment Control	
TC	Tracking Control	
WE	Wind Erosion Control	
NS	Non-Stormwater Management Control	
WM	Waste Management and Materials Pollution Control	✓

#### Legend:

- **√** Primary Objective
- ✓ Secondary Objective

#### **Description and Purpose**

Proper sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and arranging for regular service and disposal.

#### **Suitable Applications**

Sanitary septic waste management practices are suitable for use at all construction sites that use temporary or portable sanitary and septic waste systems.

#### Limitations

None identified.

#### **Implementation**

Sanitary or septic wastes should be treated or disposed of in accordance with state and local requirements. In many cases, one contract with a local facility supplier will be all that it takes to make sure sanitary wastes are properly disposed.

#### Storage and Disposal Procedures

- Temporary sanitary facilities should be located away from drainage facilities, watercourses, and from traffic circulation. When subjected to high winds or risk of high winds, temporary sanitary facilities should be secured to prevent overturning.
- Wastewater should not be discharged or buried within the project site.

	Targeted Constituents		
*	Sediment		
	Nutrients	✓	
	Trash	✓	
	Metals		
	Bacteria	✓	
	Oil and Grease		
	Organics	✓	

#### **Potential Alternatives**



# WM-9 Sanitary/Septic Waste Management

- Sanitary and septic systems that discharge directly into sanitary sewer systems, where permissible, should comply with the local health agency, city, county, and sewer district requirements.
- Only reputable, licensed sanitary and septic waste haulers should be used.
- Sanitary facilities should be located in a convenient location.
- Untreated raw wastewater should never be discharged or buried.
- Temporary septic systems should treat wastes to appropriate levels before discharging.
- If using an onsite disposal system (OSDS), such as a septic system, local health agency requirements must be followed.
- Temporary sanitary facilities that discharge to the sanitary sewer system should be properly connected to avoid illicit discharges.
- Sanitary and septic facilities should be maintained in good working order by a licensed service.
- Regular waste collection by a licensed hauler should be arranged before facilities overflow.

#### Education

- Educate employees, subcontractors, and suppliers on sanitary and septic waste storage and disposal procedures.
- Educate employees, subcontractors, and suppliers of potential dangers to humans and the environment from sanitary and septic wastes.
- Instruct employees, subcontractors, and suppliers in identification of sanitary and septic waste.
- Hold regular meetings to discuss and reinforce disposal procedures (incorporate into regular safety meetings).
- Establish a continuing education program to indoctrinate new employees.

#### Costs

All of the above are low cost measures.

## Inspection and Maintenance

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Arrange for regular waste collection.
- If high winds are expected, portable sanitary facilities must be secured with spikes or weighed down to prevent over turning.

# Sanitary/Septic Waste Management WM-9

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.

Drain Insert MP-52

#### **General Description**

Drain inserts are manufactured filters or fabric placed in a drop inlet to remove sediment and debris. There are a multitude of inserts of various shapes and configurations, typically falling into one of three different groups: socks, boxes, and trays. The sock consists of a fabric, usually constructed of polypropylene. The fabric may be attached to a frame or the grate of the inlet holds the sock. Socks are meant for vertical (drop) inlets. Boxes are constructed of plastic or wire mesh. Typically a polypropylene "bag" is placed in the wire mesh box. The bag takes the form of the box. Most box products are one box; that is, the setting area and filtration through media occur in the same box. Some products consist of one or more trays or mesh grates. The trays may hold different types of media. Filtration media vary by manufacturer. Types include polypropylene, porous polymer, treated cellulose, and activated carbon.

#### **Inspection/Maintenance Considerations**

Washout problems increase with rain intensity. Susceptibility of accumulated sediments to be re-suspended at low flow rates, can be corrected with an energy dissipater between gate and treatment areas.

Inspection Activities	Suggested Frequency
<ul> <li>Inspect for sediment buildup and proper functioning.</li> </ul>	At the beginning of the wet season and after significant storms
Verify that stormwater enters the unit and does not leak around the perimeter.	After construction.
<b>Maintenance Activities</b>	Suggested Frequency
■ Remove sediment as needed.	At the beginning of the wet season and as necessary

#### Maintenance Concerns, Objectives, and Goals

■ Sediment Removal

#### **Targeted Constituents**


- ✓ Sediment
- ✓ Nutrients
- Trash
- Metals
  Bacteria
- ✓ Oil and Grease
- ✓ Organics

#### Removal Effectiveness

See New Development and Redevelopment Handbook-Section 5.








## FloGard<sup>®</sup>

A multi-model flexible-body catch basin insert designed to collect silt, debris and petroleum hydrocarbons from water runoff.

The working chamber of the FloGard<sup>®</sup> is made of durable geotextile fabric which is easily replaced and provides for flexibility, ease of maintenance and economy. It is designed to collect silt and debris, as well as petroleum hydrocarbons (oils and greases). As with all FloGard<sup>®</sup> series filters, the standard FloGard<sup>®</sup> performs as an effective filtering device at low flows ("first flush") and, because of the built-in high flow bypass, will not impede the system's maximum design flow.

FloGard<sup>®</sup> inserts are available in sizes to fit most industry-standard drainage inlets (...flat grated, combination, curb and round inlets).

FloGard® catch basin inserts are recommended for areas subject to silt and debris as well as low-to-moderate levels of petroleum hydrocarbon (oils and grease). Examples of such areas are vehicle parking lots, aircraft ramps, truck and bus storage yards, corporation yards, subdivision streets and public streets.



Model No.	Inlet I.D.	Grate O.D.	Solids Storage Cap. (cu ft)	Filtered Flow (cfs)	Total Bypass Cap. (cfs)
FF-12D	12" x 12"	14" x 14"	0.3	0.5	0.2
FF-V64D	14" x 14"	16" x 16"	0.3	0.5	0.2
FF-16D	16" x 16"	18" x 18"	0.5	0.8	0.4
FF-1624D	16" x 24"	16" x 26"	0.6	1.1	0.6
FF-18D	18" x 18"	20" x 20"	0.5	0.9	0.5
FF-1824D	18" x 24"	20" x 24"	0.6	1.1	0.6
FF-1836SD	18" x 36"	18" x 40"	1.0	1.7	1.1
FF-1836DGO	18" x 36"	18" x 40"	1.0	1.7	1.1
FF-1848DGO	48" x 48"	18" x 52"	1.2	2.1	1.4
FF-21D	22" x 22"	24" x 24"	0.7	1.2	0.7
FF-24D	24" x 24"	26" x 26"	0.8	1.4	0.9
FF-24DGO	24" x 24"	18" x 36"	0.8	1.4	0.9
FF-2430D	24" x 30"	26" x 30"	1.0	1.7	1.1
FF-2436D	24" x 36"	24" x 40"	1.1	1.9	1.3
FF-2436DGO	24" x 36"	24" x 40"	1.1	1.9	1.3
FF-2448D(2pc)	24" x 48"	26" x 48"	1.3	2.3	1.6
FF-30D	30" x 30"	30" x 34"	1.1	1.9	1.3
FF-36D(2pc)	36" x 36"	36" x 40"	1.3	2.3	1.6
FF-3648D(2pc)	36" x 48"	40" x 40"	1.6	2.7	1.9
FF-48D (2 pc)	48" × 48"	48" x 52"	1.8	3.2	2.3

#### NOTES:

- Storage capacity reflects 80% of maximum solids collection prior to bypass.
- 2. Filtered flow rate includes a safety factor of 2.
- FloGard® Catch Basin Filter inserts are available in the standard sizes (see above) or in custom sizes.
   Call for details on custom size inserts.
- FloGard® filter inserts should be used in conjunction with a regular maintenance program. Refer to manufacturer's recommended maintenance guidelines.

# FLOGARD® CATCH BASIN FILTER INSERT

(Frame Mount)

**FLAT GRATED INLET** 

KriStar Enterprises, Inc., Santa Rosa, CA (800) 579-8819

12/04

# Test Results FloGard® and FloGard+PLUS<sup>TM</sup>

# Oil and Grease and Particle Removal by KriStar Flo-Gard and Flo-Gard High Capacity Stormdrain Inserts

by Michael K. Stenstrom Sim-Lin Lau

Civil and Environmental Engineering Department University of California, Los Angeles 4173 Engineering I Los Angeles, CA 90095-1593

February 20, 2002

#### Summary

A series of experiments was performed in a small but full-scale catch basin simulator to determine the efficiency of various Kristar (Fossil Filter) catch basin inserts to remove oil and grease and suspended solids. Catch basin inserts are devices used in stormwater collection systems to remove various pollutants, including suspended solids, litter and oil and grease. Devices from several other manufacturers have also been tested in this same facility. This work builds upon an earlier project to develop catch basin inserts, which was funded in part by the Santa Monica Bay Restoration Project and in part by a consortium of cities and agencies.


All experiments were conducted in a full-scale "mock" catch basin (36 inch wide opening) located in a laboratory at UCLA. The catch basin is constructed of plywood and stands above grade to allow easy access and installation of prototype devices. The catch basin operates with tap water at flow rates from near zero to 200 gallons per minute (GPM). Various levels of contaminants can be added to the influent to simulate stormwater.

Tests were performed on two types of inserts, called FloGard<sup>TM</sup> and FloGard<sup>TM</sup> High Capacity, over flow rates ranging from 15 to 25 gallons per minute (GPM). Testing was performed to determine oil and grease removal rate for influent concentrations that varied from 16 mg/L to 36 mg/L for time periods from 30 to 180 minutes. Total suspended solids (TSS) removal was evaluated for concentrations from 65 to 100 mg/L for 30minute periods. Automobile crank case oil was used to simulate oil and grease in stormwater. Graded sand was used to simulate TSS in stormwater. Two types of sorbents were used for the oil and grease studies: Fossil Rock<sup>TM</sup>, an aluminum silicate sorbent, and Rubberizer<sup>TM</sup>, an organic polymer. Both are commercially available for this and other applications.

Oil and grease removal efficiency ranged from 70 to 80% for most conditions. Sand removal was nearly 100% for particles 30 mesh (589 to 833 mm) and larger, 20% for particles 60 mesh (250 to 420 mm) and nearly zero for smaller particles.

### **Experimental Methods**

Figure 1 show is a schematic diagram of the experimental facility. Building water (tap water) is connected to the catch basin simulator via a 3-inch diameter pipe. Two flow meters are provided. The first is an ultrasonic flow meter (Dynasonic UST-603, Naperville, IL) that uses Doppler effect to determine the velocity of flowing particles. From the velocity and known pipe diameter, the flow is calculated. In this application, there are too few particles in the tap water and a small quantity of air is added to simulate particles. A second flow meter (Signet +GF+, Cole-Parmer, Chicago, IL) using a paddle wheel is also used. The paddle wheel rotations are counted and the flow rate is proportional to the rotations; different calibrations are provided for different pipe diameters.



The ultrasonic meter is used for higher flows while the paddle wheel meter is more convenient for low flows. The paddle wheel meter was generally used during these experiments.

The pipe connects to the stilling basin, which discharges into a 24 inch-wide flume. The purpose of the stilling basin is to dampen velocities from the inlet as well as to insure a constant flow rate. The flume is 10 feet long and connects to the catch basin. All contaminants (oil and grease, sand, etc.) were introduced into the 24-inch flume. Liquids were pumped into the flume using a peristaltic metering pump. The sand was "sprinkled" into the flow from preweighed sample bottles over 1 or 2-minute intervals. In this way the appropriate amounts of sand were released every one or two minutes. This process was continued throughout the test. The flume provides adequate mixing to disperse all materials.

#### **Test Sequence**

Influent samples were collected from the free surface as the water spilled into the inlet device. Effluent samples were collected by passing glass sample bottles below the inlet device. Tests were begun by collecting a influent sample prior to the introduction of any contaminants to the flume. Next the metering pump was turned on. Effluent samples were collected periodically for the test duration. Generally 10 to 12 samples were collected for each test, and samples were evenly distributed over time. Two additional influent samples were collected at times equal to approximately one-third and two-thirds of the test duration.

At the end of the test, the metering pump was turned off. In previous testing sampling continued for 30 minutes after ending oil and grease addition. For aluminum silicate, Rubberizer and OARs sorbents at the concentrations used in these studies, it was shown that no measurable oil and grease desorbs. In some cases the sorbents were reused, which simulates sequential rainfall. For these tests, the sorbent was allowed to dry but was not modified in anyway. Samples were generally analyzed within 16 hours after the tests were completed.

### Oil and grease removal test

Tests were generally performed for 30 minutes (see Table 1 for a summary of all tests). Used crankcase lubricating oil (from automobiles) was used as the oil and grease source. One batch was used for all tests. Influent oil and grease samples were collected as the oil/water combination flowed into the insert. Effluent samples were collected by capturing flow from the bottom of the insert. Efficiencies were calculated by subtracting the measured effluent concentrations from the average influent concentration. All tests were performed at constant flow rate.

Oil and Grease Analysis. Oil and grease was measured using a solid phase extraction (SPE) technique developed earlier by the authors (Lau and Stenstrom, 1997). This technique uses a known volume of sample (generally 500 ml for this study), which is pumped through an SPE column at a constant but low rate (e.g., 5 ml/min). The oil and grease in the sample is sorbed on the SPE column. After the sample is pumped through the column, it is eluted with a small volume of solvent (5 ml):methylene chloride and hexane. The sample bottle is also washed with a small volume of isopropanol. The two solvent volumes are combined and placed in a tarred container. The solvents are allowed to dry at 50°C using a gentle nitrogen purge. The residue is weighed and the results are reported as mg/L based upon the original sample volume. This method has the advantages of higher recovery, especially for the more volatile components in oil and grease, and using less solvent. By using different sample volumes is it possible to have different detection limits, and the limit with 500-ml sample volume is typically 0.25 mg/L. This method does not quantitatively measure oil and grease adsorbed to solids and an alternate technique must be used for particle-bound oil and grease. However, this is not important for this study because no particles where added to the tap water used for oil and grease testing.

#### Sand particle removal test

Sand particles were prepared by sieving sands from various sources, but mostly from sand used for concrete construction. A series of ASTM standard sieves were used. Particles were selected to demonstrate removal efficiency, as opposed to simulate particles found in stormwater. For the screen provide in the high capacity FloGard<sup>TM</sup>, sieve sizes of 20, 30, 40, 60 and 100 (2000, 833, 589, 420, 250, 149 mm respectively)were selected. Equal, known masses of each sand particle size were released into the flume over a 30 minute test which flowed into the insert. Below the insert, a fine screen, corresponding to 325 mesh (45 mm), captured the particles not removed by the insert. At the end of the test, the 325-mesh screen was removed and the retained sand particles were collected, dried, sieved and weighed. The weight of recovered particles in each sieve size was compared to the amount of sand released into the flume to calculate efficiency. As expected the large particles were removed well, while the smaller particles were removed poorly. The smallest sand particles are smaller than the mesh openings.

Three sand removal tests were performed. One was performed at 25 gallons per minute (GPM) and two were performed at 15 GPM. Sand was added to create influent concentrations equal to 65 to  $100~\rm mg/L$ 

#### Inserts

The two inserts tested were standard units and were modified only to allow them to be accurately positioned in the simulated catch basin. This required the end brackets to be modified to allow attachment. The pollutant removal parts of the inserts (e.g., sorbent pouches, screens) were not modified. The FloGard™ insert measured 35 inches long by 22 inches wide and was open in the middle. The opening was 27 inches long and 15 inches wide. The area between the opening and the outside dimensions is a trough of screen and contained 6 pouches or "sausages" of sorbent. The opening is provided to allow high flows to bypass. The sorbent pouches can be replaced in both models without removing the insert. The FloGard™ high capacity insert was 35 inches long by 17 inches deep. The central section is fully enclosed and forms a bag that retains litter and debris. The internal dimensions are 32 long by 12 inches wide, and the bag is 28 inches deep. Sorbent pouches (12) are one was screen, just like the walls, while the other was non-woven polypropylene. Manufacturer's literature should be consulted for more precise information.

Table 1. Oil and grease removal test conditions used.

Test No.	Insert Type	Sorbent	Flow rate (GPM)	Duration (min)	Influent conc. (mg/L)
1	FloGard™ High Capacity	Fossil Rock	15	30	16
2	From test 1		15	30	29
3	From test 2		15	180	26
4	Flo-Gard	Fossil Rock	15	30	34

5	From test 4		15	30	34
6	From test 5		15	180	34
7	FloGard™ High Capacity, non-woven bottom	Rubberizer	15	30	36
8	From test 7		15	30	31
9	From test 8		15	180	23
10	FloGard™ High Capacity	Rubberizer	15	30	22
11	From test 10		15	30	24
12	From test 11		15	180	30

Table 2. Particle removal test conditions used.

Test No.	Insert Type	Mesh No.	Particle size (um)	Flow rate (GPM)	Duration (min)	Influent conc. (mg/L)
13	FloGard <sup>™</sup> High Capacity	20, 30, 40, 60, 100	2000, 833, 589, 420, 250, 149	15	30	65
14	FloGard™ High Capacity	20, 30. 40, 60, 100	2000, 833, 589, 420, 250, 149	15	30	100
15	FloGard™ High Capacity	20, 30. 40, 60, 100	2000, 833, 589, 420, 250, 149	25	30	65
16	FloGard™	20, 30, 40, 60, 100	2000, 833, 589, 420, 250, 149	15	30	65
17	FloGard™	20, 30, 40, 60, 100	2000, 833, 589, 420, 250, 149	15	30	100
18	FloGard™	20, 30, 40, 60, 100	2000, 833, 589, 420, 250, 149	25	30	65
19	FloGard™ High Capacity, non-woven bottom	20, 30, 40, 60, 100	2000, 833, 589, 420, 250, 149	25	30	65
20	FloGard™ High Capacity, non-woven bottom	60, 100, 200	250, 149, 75	25	30	65

# Back to Top of Page

#### **Results and Discussion**

Figure 2 (top) shows the results of the first two series of test (3 tests each). Two insert configurations (FloGard<sup>TM</sup> and FloGard<sup>TM</sup> High Capacity) were evaluated. Both used aluminum silicate (Fossil Rock) sorbents. The first two tests for each insert were conducted over a 30-minute period. The third test was conducted over a 180-minute period. The first two tests were used to establish the removal efficiency of the unit. The third test was performed to see if any decline in removal efficiency would occur due to saturation of the sorbent.

The initial removal efficiency of both inserts was approximately 85% and decline slightly during the first 60 minutes. The high capacity unit showed less decline in removal rate after the third test, as expected. The normal capacity unit declined to approximately 60% removal after 240 minutes, while the high capacity insert decline to 70%. The high capacity insert has greater sorbent mass and has greater volume for litter and debris retention.

Rubberizer sorbent was also used in the high capacity insert. Rubberizer has greater specific gravity than aluminum silicate (0.10 to 0.13 for aluminum silicate versus 0.26 for Rubberizer). Rubberizer has less tendency to abrade than aluminum silicate sorbents. Both have particles sizes approximately 2 to 3 mm. Sorbent pouches containing Rubberizer were substituted in each insert in exactly the same way as aluminum silicate pouches were used. Figure2 (middle) compares the removal efficiencies with Rubberizer and aluminum silicate. The Rubberizer has lower initial removal efficiency, but declines less over time. After 240 minutes, the efficiency of both sorbents was approximately 70%.

Figure 2 (bottom) compares a modified screen to a normal screen using Rubberizer as sorbents. The difference in the screen is the bottom construction. The modified screen has a non-woven bottom composed of polypropylene mesh. The polypropylene mesh is also a good oil and grease sorbent. It has a very fine mesh and is more subject to clogging than the more open screen. The non-woven bottom produces higher efficiency during the initial phases of the tests, and approximates the same removal efficiency as aluminum silicate sorbent.

Figures 3 and 4 show the particle removal rates of FloGard<sup>TM</sup> and FloGard<sup>TM</sup> High Capacity inserts. Sand was sieved using ASTM screens to produce the particle size groupings shown on the horizontal axis of each graph. Sieves were chosen to select particles that were larger, equal to and less than the nominal screen size openings. Figure 5 shows a photomicrograph of the mesh with a millimeter ruler, and both inserts used the same size mesh. The openings are approximately 500 mm. The elongated openings at the surface of the ruler are an artifact of cutting the mesh.

Removal rates are consistent with the average mesh opening (500 mm). Particles much larger(580 to 2,000 mm) were almost completely removed. Very little removal occurred with smaller particles smaller than 420 mm. Removal rates at higher flow rates or concentrations were slightly higher, suggesting that accumulation of particles at the screen might be forming a "dynamic" filter. Head loss for the flows and amounts of particles removed were not observably different from head loss without particles. More accumulation of particles would be necessary to observe head loss.

#### **Conclusions**

The performance of these two devices is consistent with the better devices tested in our laboratory (Lau, Khan and Stenstrom, 2001). The differences in performance, as measured by these tests is small, and the selection of products could be based upon other considerations, such as cost, durability and potential for clogging.




Figure 2. Oil and grease removal efficiency of FloGard™ insert (tests 1-12).




Figure 3. Particle removal efficiency of FloGard<sup>TM</sup> insert (tests 16-18).




Figure 4. Particle removal efficiency of FloGard™ High Capacity (tests 13-15).




Figure 5.

#### References

Lau, S-L. and M. K. Stenstrom, "Application of Oil Sorbents in Oil and Grease Removal from Stormwater Runoff," Proceedings of the 68th Annual Water Environment Federation Conference and Exposition, Miami Beach, FL, October 21-25, # 9572008, Vol. 3, pp. 685-695, 1995.

Lau, S-L. and M.K. Stenstrom, "Solid Phase Extraction for Oil and Grease Analysis," *Water Environment Research*, Vol. 69, No. 3, pp. 368-374, 1997.

Lau S-L., E. Khan, and M.K. Stenstrom, "Catch Basin Inserts to Reduce Pollution from Stormwater," *Water Science and Technology*, Vol. 44, pp. 23-34., 2001.

# Back to Top of Page

# ATTACHMENT F HYDROLOGY STUDY



# HYDROLOGY STUDY

FOR

STARCO FOOD MART S06-026 LOG No. 06-19-021

IN

COUNTY OF SAN DIEGO

JN 05-007

APRIL 17, 2006

No. 43235
Exp. 3-31-08

CIVILOF CALIFORNIA

HOSSEINS ZOMORRODI R.C.E. 43235

4/17/0 G DATE

# TABLE OF CONTENTS

1.	INTRO	ODUCTION	
		EXISTING CONDITION PROPOSED CONDITION	
2.	VICIN:	ITY MAP	
3.	HYDRO!	LOGY DESIGN MODELS	

4.HYDROLOGIC CALCULATIONS ..... APPENDIX A

5. TABLES AND CHARTS ..... APPENDIX B

6.HYDROLOGY MAPS ..... APPENDIX C

# 1. INTRODUCTION

# A. EXISTING CONDITION

The site is located on the north side of Jamacha Boulevard in the County of San Diego, currently the site consists of a vacant pregraded parcel (0.54Ac), relatively flat with a small slope facing on Jamacha Blvd and Pecos Street. The overland flow path drains southwesterly and southeasterly of the property and the total runoff generated is 0.84CFS

# B. PROPOSED CONDITION

The proposed development consist of a gas station with is corresponding food mart, fueling station, trash enclosure and parking areas. The proposed sheet flow drains southwesterly and southeasterly of the property and intercepted by two grated catch basin connected to a curb outlet which will exit to the public curb and gutter. Total runoff generated is 2.48CFS

# 3. HYDROLOGY DESIGN MODELS

#### A. DESIGN METHODS

THE RATIONAL METHOD IS USED IN THIS HYDROLOGY STUDY; THE RATIONAL FORMULA IS AS FOLLOWS:

- Q = CIA, WHERE : Q= PEAK DISCHARGE IN CUBIC FEET/SECOND \*
- C = RUNOFF COEFFICIENT (DIMENSIONLESS)
- I = RAINFALL INTENSITY IN INCHES/HOUR
- A = TRIBUTARY DRAINAGE AREA IN ACRES
- \*1 ACRE INCHES/HOUR = 1.008 CUBIC FEET/SEC

THE OVERLAND METHOD IS ALSO USED IN THIS HYDROLOGY STUDY; THE URBAN AREAS OVERLAND FORMULA IS AS FOLLOWS:

- $T=[1.8(1.1-C)(L)^{(.5)})]/[S(100)]^{.333}$
- L = LENGTH OF WATERSHED
- C = COEFFICIENT OF RUNOFF
- T = TIME IN MINUTES
- S = DIFFERENCE IN ELEVATION DIVIDED BY DE LENGTH OF WATERSHED

# B. DESIGN CRITERIA

- FREQUENCY, 100 YEAR STORM.
- LAND USE PER SPECIFIC PLAN AND TENTATIVE MAP.
- RAIN FALL INTENSITY PER COUNTY OF SAN DIEGO 2003 HYDROLOGY DESIGN MANUAL.

#### C. REFERENCES

- COUNTY OF SAN DIEGO 2003, HYDROLOGY DESIGN MANUAL.
- COUNTY OF SAN DIEGO 2003 REGIONAL STANDARD DRAWING.
- HAND BOOK OF HYDRAULICS BY BRATER & KING, SIXTH EDITION.

# APPENDIX A

(4. HYDROLOGIC CALCULATIONS)

#### EXISTING CONDITION

San Diego County Rational Hydrology Program

```
CIVILCADD/CIVILDESIGN Engineering Software, (c) 1991-2004 Version 7.4
Rational method hydrology program based on
San Diego County Flood Control Division 2003 hydrology manual
    Rational Hydrology Study Date: 05/01/06
******* Hydrology Study Control Information ********
-----
                                        05-007UND
Program License Serial Number 4035
_____
Rational hydrology study storm event year is 100.0
English (in-lb) input data Units used
Map data precipitation entered:
6 hour, precipitation(inches) = 2.900
24 hour precipitation(inches) = 5.800
P6/P24 = 50.0%
San Diego hydrology manual 'C' values used
Process from Point/Station 1.000 to Point/Station 2.000
**** INITIAL AREA EVALUATION ****
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[UNDISTURBED NATURAL TERRAIN
(Permanent Open Space )
Impervious value, Ai = 0.000
Sub-Area C Value = 0.350
 Initial subarea total flow distance = 50.000(Ft.)
Highest elevation = 331.600(Ft.)
 Lowest elevation = 330.110(Ft.)
 Elevation difference = 1.490(Ft.) Slope = 2.980 \pm
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 100.00 (Ft)
for the top area slope value of 2.98 %, in a development type of
 Permanent Open Space
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 9.38 minutes
TC = [1.8*(1.1-C)*distance(Ft.)^.5)/(% slope^(1/3)]
TC = [1.8*(1.1-0.3500)*(100.000^.5)/(2.980^(1/3)] = 9.38
 Rainfall intensity (I) = 5.092(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is C = 0.350
 Subarea runoff = 0.105(CFS)
                            0.059(Ac.)
 Total initial stream area =
 Process from Point/Station 2.000 to Point/Station 3.000
 **** IMPROVED CHANNEL TRAVEL TIME ****
 Upstream point elevation = 330.110(Ft.)
 Downstream point elevation = 328.900(Ft.)
 Channel length thru subarea = 64.000(Ft.)
 Channel base width = 0.000(Ft.)
 Slope or 'Z' of left channel bank = 80.000
 Slope or 'Z' of right channel bank = 80.000
```

```
Estimated mean flow rate at midpoint of channel = 0.299(CFS)
Manning's 'N' = 0.035
Maximum depth of channel = 0.500(Ft.)
Flow(q) thru subarea = 0.299(CFS)
Depth of flow = 0.075(Ft.), Average velocity = 0.657(Ft/s)
Channel flow top width = 12.078(Ft.)
                 0.66(Ft/s)
Flow Velocity =
Travel time = 1.62 min.
Time of concentration = 11.01 min.
Critical depth = 0.062(Ft.)
Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[UNDISTURBED NATURAL TERRAIN
(Permanent Open Space )
Impervious value, Ai = 0.000
Sub-Area C Value = 0.350
Rainfall intensity = 4.593(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.350 CA = 0.097
Subarea runoff = 0.340(CFS) for 0.218(Ac.)
Total runoff = 0.445(CFS) Total area = 0.277(Ac.)
Total runoff = 0.445 (CFS) Total area = 0.277 (Ac.)
Depth of flow = 0.088 (Ft.), Average velocity = 0.725 (Ft/s)
Critical depth = 0.072 (Ft.)
 Process from Point/Station 1.000 to Point/Station 4.000
 **** INITIAL AREA EVALUATION ****
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
                                            1
 [UNDISTURBED NATURAL TERRAIN
 (Permanent Open Space )
 Impervious value, Ai = 0.000
 Sub-Area C Value = 0.350
 Initial subarea total flow distance = 50.000(Ft.)
 Highest elevation = 331.600(Ft.)
 Lowest elevation = 330.650(Ft.)
 Elevation difference = 0.950(Ft.) Slope = 1.900 %
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 85.00 (Ft)
 for the top area slope value of 1.90 %, in a development type of
  Permanent Open Space
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 10.05 minutes
 TC = [1.8*(1.1-C)*distance(Ft)^.5)/(% slope^(1/3)]
 TC = [1.3*(1.1-0.3500)*(-85.000^{\circ}.5)/(-1.900^{\circ}(1/3)] = -10.05
 Rainfall intensity (I) = 4.871(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is C = 0.350
 Subarea runoff = 0.053(CFS)
                                  0.031(Ac.)
 Total initial stream area =
  Process from Point/Station 4.000 to Point/Station 5.000
  **** IMPROVED CHANNEL TRAVEL TIME ****
```

```
Upstream point elevation = 330.650(Ft.)
Downstream point elevation = 327.500(Ft.)
Channel length thru subarea = 96.000(Ft.)
Channel base width = 0.000(Ft.)
Slope or 'Z' of left channel bank = 80.000
Slope or 'Z' of right channel bank = 80.000
Estimated mean flow rate at midpoint of channel = 0.228(CFS)
Manning's 'N' = 0.035
Maximum depth of channel = 0.500(Ft flow(q) thru subarea = 0.228(CFS)
                              0.500(Ft.)
Depth of flow = 0.062(Ft.), Average velocity = 0.755(Ft/s)
Channel flow top width = 9.841(Ft.)
Flow Velocity = 0.75(Ft/s)
Travel time = 2.12 min.
Time of concentration = 12.17 min.
Critical depth = 0.055(Ft.)
 Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [UNDISTURBED NATURAL TERRAIN
 (Permanent Open Space )
 Impervious value, Ai = 0.000
 Sub-Area C Value = 0.350
 Rainfall intensity = 4.305(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.350 CA = 0.083
 Subarea runoff = 0.304(CFS) for 0.206(Ac.)

Total runoff = 0.357(CFS) Total area = 0.237(Ac.)

Depth of flow = 0.073(Ft.), Average velocity = 0.844(Ft/s)
 Critical depth = 0.066(Ft.)
 Process from Point/Station 6.000 to Point/Station 7.000
 **** INITIAL AREA EVALUATION ****
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
                                             1
  [UNDISTURBED NATURAL TERRAIN
  (Permanent Open Space )
  Impervious value, Ai = 0.000
  Sub-Area C Value = 0.350
  Initial subarea total flow distance = 50.000(Ft.)
  Highest elevation = 330.700(Ft.)
Lowest elevation = 329.900(Ft.)
  Elevation difference = 0.800(Ft.) Slope = 1.600 	{3}
  INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
  The maximum overland flow distance is 85.00 (Ft)
  for the top area slope value of 1.60 %, in a development type of
   Permanent Open Space
  In Accordance With Figure 3-3
  Initial Area Time of Concentration = 10.64 minutes
  TC = [1.8*(1.1-C)*distance(Ft.)^.5)/(% slope^(1/3)]
  TC = [1.8*(1.1-0.3500)*(85.000^.5)/(1.600^(1/3)] = 10.64
  Rainfall intensity (I) = 4.694(In/Hr) for a 100.0 year storm
  Effective runoff coefficient used for area (Q=KCIA) is C = 0.350
  Subarea runoff = 0.046(CFS)
                                     0.028(Ac.)
  Total initial stream area =
  End of computations, total study area =
                                                  0.542 (Ac.)
```

#### PROPOSED CONDITION

San Diego County Rational Hydrology Program

```
CIVILCADD/CIVILDESIGN Engineering Software, (c) 1991-2004 Version 7.4
Rational method hydrology program based on
San Diego County Flood Control Division 2003 hydrology manual
    Rational Hydrology Study Date: 05/01/06
_____
******* Hydrology Study Control Information ********
-----
Program License Serial Number 4035
-----
Rational hydrology study storm event year is 100.0
English (in-lb) input data Units used
Map data precipitation entered:
6 hour, precipitation(inches) = 2.300
24 hour precipitation(inches) = 4.600
P6/P24 = 50.0%
San Diego hydrology manual 'C' values used
Process from Point/Station 1.000 to Point/Station 2.000
**** INITIAL AREA EVALUATION ****
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[COMMERCIAL area type
(General Commercial
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Initial subarea total flow distance = 50.000(Ft.)
Highest elevation = 331.300(Ft.)
Lowest elevation = 330.300(Ft.)
Elevation difference = 1.000(Ft.) Slope = 2.000 %
Top of Initial Area Slope adjusted by User to 0.500 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 50.00 (Ft)
for the top area slope value of 0.50 %, in a development type of
 General Commercial
In Accordance With Figure 3-3
Initial Area Time of Concentration = 4.49 minutes
TC = [1.8*(1.1-C)*distance(Ft.)^.5)/(% slope^(1/3)]
TC = [1.8*(1.1-0.8200)*(50.000^{5})/(0.500^{(1/3)}] = 4.49
Rainfall intensity (I) = 6.495(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.820
Subarea runoff = 0.245(CFS)
                            0.046(Ac.)
Total initial stream area =
Process from Point/Station 2.000 to Point/Station 3.000
**** IMPROVED CHANNEL TRAVEL TIME ****
Upstream point elevation = 330.300(Ft.)
Downstream point elevation = 329.780(Ft.)
Channel length thru subarea = 94.330(Ft.)
Channel base width = 0.000(Ft.)
```

```
Slope or 'Z' of left channel bank = 80.000
Slope or 'Z' of right channel bank = 80.000
Estimated mean flow rate at midpoint of channel = 0.579(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 0.500(Ft.)
Flow(q) thru subarea = 0.579(CFS)
Depth of flow = 0.089(Ft.), Average velocity = 0.921(Ft/s)
Channel flow top width = 14.185(Ft.)
Flow Velocity = 0.92(Ft/s)
Travel time = 1.71 \text{ min.}
Time of concentration = 6.20 min.
Critical depth = 0.080(Ft.)
 Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[COMMERCIAL area type
(General Commercial
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Rainfall intensity = 5.277(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.820 CA = 0.155
Subarea runoff = 0.573 (CFS) for 0.143 (Ac.)
Total runoff = 0.818 (CFS) Total area = 0.189 (Ac.)
Total runoff =
Depth of flow = 0.101(Ft.), Average velocity = 1.004(Ft/s)
Critical depth =
                    0.092(Ft.)
Process from Point/Station 3.000 to Point/Station 4.000
**** PIPEFLOW TRAVEL TIME (User specified size) ****
Upstream point/station elevation = 327.780(Ft.)
Downstream point/station elevation = 327.020(Ft.)
Pipe length = 24.68(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 0.818(CFS)
Given pipe size = 6.00(In.)
Calculated individual pipe flow = 0.818(CFS)
Normal flow depth in pipe = 4.17(In.)
Flow top width inside pipe = 5.52(In.)
Critical Depth = 5.37(In.)
Pipe flow velocity = 5.61(Ft/s)
Travel time through pipe = 0.07 min.
Time of concentration (TC) = 6.27 \text{ min.}
Process from Point/Station 3.000 to Point/Station
**** SUBAREA FLOW ADDITION ****
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
                                            ]
 [COMMERCIAL area type
 (General Commercial
 Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Time of concentration = 6.27 min.

Rainfall intensity = 5.237(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
```

```
(Q=KCIA) is C = 0.820 CA = 0.206
Subarea runoff = 0.260(CFS) for 0.062(Ac.)
Total runoff = 1.078(CFS) Total area = 0.251(Ac.)
Process from Point/Station 4.000 to Point/Station
**** IMPROVED CHANNEL TRAVEL TIME ****
Covered channel
Upstream point elevation = 327.020(Ft.)
Downstream point elevation = 326.780(Ft.)
Channel length thru subarea = 12.000(Ft.)
Channel base width = 3.000(Ft.)
Slope or 'Z' of left channel bank = 100.000
Slope or 'Z' of right channel bank = 100.000
Estimated mean flow rate at midpoint of channel = 1.078(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 0.250(Ft.)
Flow(q) thru subarea = 1.078(CFS)
Depth of flow = 0.068(Ft.), Average velocity = 1.636(Ft/s)
Channel flow top width = 16.508(Ft.)
Flow Velocity = 1.64(Ft/s)
Travel time = 0.12 min.
Time of concentration = 6.39 min.
Critical depth = 0.080(Ft.)
 Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[COMMERCIAL area type
(General Commercial
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
The area added to the existing stream causes a
a lower flow rate of Q = 1.064(CFS)
                                         1.078(CFS) is being used
therefore the upstream flow rate of Q =
Rainfall intensity = 5.172(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.820 CA = 0.206
Subarea runoff = 0.000(CFS) for 0.000(Ac.)
Total runoff = 1.078(CFS) Total area = 0.251(Ac.)
Total runoff = 1.078 (CFS) Total area = 0.251 (AC.)
Depth of flow = 0.068 (Ft.), Average velocity = 1.636 (Ft/s)
Critical depth =
                   0.080(Ft.)
 Process from Point/Station 1.000 to Point/Station 6.000
 **** INITIAL AREA EVALUATION ****
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
                                           ]
 [COMMERCIAL area type
 (General Commercial
 Impervious value, Ai = 0.850
 Sub-Area C Value = 0.820
 Initial subarea total flow distance = 50.000(Ft.)
 Highest elevation = 331.300(Ft.)
 Lowest elevation = 330.310(Ft.)
 Elevation difference = 0.990(Ft.) Slope = 1.980 %
```

```
Top of Initial Area Slope adjusted by User to 0.500 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 50.00 (Ft)
for the top area slope value of 0.50 %, in a development type of
General Commercial
In Accordance With Figure 3-3
Initial Area Time of Concentration = 4.49 minutes
TC = [1.8*(1.1-C)*distance(Ft.)^{.5})/(*slope^{(1/3)}]

TC = [1.8*(1.1-0.8200)*(50.000^{.5})/(0.500^{(1/3)}] = 4.49
Rainfall intensity (I) = 6.495(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.820
Subarea runoff = 0.234(CFS)
                                 0.044 (Ac.)
Total initial stream area =
Process from Point/Station 6.000 to Point/Station 7.000
**** IMPROVED CHANNEL TRAVEL TIME ****
Upstream point elevation = 330.310(Ft.)
Downstream point elevation = 329.800(Ft.)
Channel length thru subarea = 80.000(Ft.)
Channel base width = 0.000(Ft.)
Slope or 'Z' of left channel bank = 80.000
Slope or 'Z' of right channel bank = 80.000
Estimated mean flow rate at midpoint of channel = 0.502(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 0.500(Ft.)
Flow(q) thru subarea = 0.502(CFS)
Depth of flow = 0.082(Ft.), Average velocity = 0.938(Ft/s)
Channel flow top width = 13.080(Ft.)
                0.94(Ft/s)
Flow Velocity =
Travel time = 1.42 min.
Time of concentration = 5.91 min.
Critical depth = 0.075(Ft.)
 Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
                                           1
 [COMMERCIAL area type
 (General Commercial
 Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
                        5.440(In/Hr) for a 100.0 year storm
Rainfall intensity =
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.820 CA = 0.129
Subarea runoff = 0.466(CFS) for 0.113(Ac.)

Total runoff = 0.700(CFS) Total area = 0.157(Ac.)

Depth of flow = 0.093(Ft.), Average velocity = 1.020(Ft/s)
                    0.086(Ft.)
 Critical depth =
 Process from Point/Station 7.000 to Point/Station 8.000
 **** PIPEFLOW TRAVEL TIME (User specified size) ****
 Upstream point/station elevation = 327.050(Ft.)
 Downstream point/station elevation = 325.750(Ft.)
 Pipe length = 19.54(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 0.700(CFS)
 Given pipe size = 6.00(In.)
```

```
Calculated individual pipe flow =
Normal flow depth in pipe = 2.94(In.)
Flow top width inside pipe = 6.00(In.)
Critical Depth = 5.07(In.)
Pipe flow velocity = 7.31(Ft/s)
Travel time through pipe = 0.04 min.
Time of concentration (TC) = 5.96 min.
Process from Point/Station 7.000 to Point/Station
**** SUBAREA FLOW ADDITION ****
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
                                         ]
[COMMERCIAL area type
(General Commercial
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Time of concentration = 5.96 min.

Rainfall intensity = 5.414(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.820 CA = 0.187
Subarea runoff = 0.312(CFS) for 0.071(Ac.)
                 1.012(CFS) Total area = 0.228(Ac.)
Total runoff =
Process from Point/Station 8.000 to Point/Station 9.000
**** IMPROVED CHANNEL TRAVEL TIME ****
Covered channel
Upstream point elevation = 325.750(Ft.)
Downstream point elevation = 325.510(Ft.)
Channel length thru subarea = 12.000(Ft.)
Channel base width = 3.000(Ft.)
Slope or 'Z' of left channel bank = 100.000
Slope or 'Z' of right channel bank = 100.000
Estimated mean flow rate at midpoint of channel =
                                                1.012(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 0.208(Ft.)
Flow(q) thru subarea = 1.012(CFS)
Depth of flow = 0.066(Ft.), Average velocity = 1.610(Ft/s)
Channel flow top width = 16.139(Ft.)
Flow Velocity = 1.61(Ft/s)
Travel time = 0.12 min:
Time of concentration = 6.08 min.
Critical depth =
                 0.078(Ft.)
 Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
                                         1
[COMMERCIAL area type
(General Commercial
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
The area added to the existing stream causes a
a lower flow rate of Q = 0.999(CFS)
therefore the upstream flow rate of Q = 1.012(CFS) is being used
Rainfall intensity = 5.342(In/Hr) for a 100.0 year storm
```

```
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.820 CA = 0.187
Subarea runoff = 0.000(CFS) for
                                     0.000(Ac.)
Total runoff = 1.012(CFS) Total area = 0.228(Ac.)
Depth of flow = 0.066(Ft.), Average velocity = 1.610(Ft/s)
Critical depth = 0.078(Ft.)
Process from Point/Station 7.000 to Point/Station 12.000
**** INITIAL AREA EVALUATION ****
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
                                          ]
[COMMERCIAL area type
(General Commercial
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Initial subarea total flow distance = 65.000(Ft.)
Highest elevation = 329.800(Ft.)
Lowest elevation = 326.300(Ft.)
Elevation difference = 3.500(Ft.) Slope = 5.385 %
Top of Initial Area Slope adjusted by User to 5.300 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 90.00 (Ft)
for the top area slope value of 5.30 %, in a development type of
 General Commercial
In Accordance With Figure 3-3
Initial Area Time of Concentration = 2.74 minutes
TC = [1.8*(1.1-C)*distance(Ft.)^.5)/(% slope^(1/3)]
TC = [1.8*(1.1-0.8200)*(90.000^{.5})/(5.300^{(1/3)}] = 2.74
Rainfall intensity (I) = 8.927(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.820
Subarea runoff = 0.315(CFS)
                                0.043(Ac.)
Total initial stream area =
Process from Point/Station 10.000 to Point/Station 11.000
**** INITIAL AREA EVALUATION ****
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
                                          1
[COMMERCIAL area type
 (General Commercial
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Initial subarea total flow distance = 28.860(Ft.)
Highest elevation = 330.200(Ft.)
Lowest elevation = 329.910(Ft.)
Elevation difference = 0.290(Ft.) Slope = 1.005 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 60.00 (Ft)
for the top area slope value of 1.00 %, in a development type of
 General Commercial
In Accordance With Figure 3-3
 Initial Area Time of Concentration = 3.90 minutes
TC = [1.8*(1.1-C)*distance(Ft.)^.5)/(% slope^(1/3)]
TC = [1.8*(1.1-0.8200)*(60.000^{.5})/(1.000^{(1/3)}] = 3.90
```


Rainfall intensity (I) = 7.109(In/Hr) for a 100.0 year storm Effective runoff coefficient used for area (Q=KCIA) is C = 0.820 Subarea runoff = 0.076(CFS) Total initial stream area = 0.013(Ac.) End of computations, total study area = 0.535(Ac.)

# APPENDIX B

(5. TABLES AND CHARTS)

# Average Values of Roughness Coefficient (Manning's n)

Type of Waterway	Roughness Coefficient (n)
1. Closed Conduits (1)	
Steel (not lined) Cast Iron Aluminum Corrugated Metal (not lined)	0.015 0.015 .021 0.024 · 0.021
Corrugated Metal (2) (smooth asphalt quarterlining) Corrugated Metal (2) (smooth asphalt half lining) Corrugated Metal (smooth asphalt full lining) Concrete RCP	0.018 0.012 0.012 0.013
Clay (sewer) Asbestos Cement = PV = Drain Tile (terra cotta) Cast-in-place Pipe Reinforced Concrete Box	0.013 0.011 0.015 0.015 0.014
2. Open Channels (1)	
a. Unlined Clay Loam Sand	0.023 0.020
<ul> <li>Revetted         Gravel         Rock         Pipe and Wire         Sacked Concrete</li> </ul>	0.030 0.040 0.025 0.025
<ul> <li>c. Lined         Concrete (poured)         Air Blown Mortar (3)         Asphaltic Concrete or Bituminous Plant Mix</li> </ul>	0.014 0.016 0.018
d. Vegetated (5) Grass lined, maintained Grass and Weeds Grass lined with concrete low flow channel	.035 .045 .032
5. Pavement and Gutters (1) Concrete Bituminous (plant-mixed)	0.015 0.016



Rational Formula - Overland Time of Flow Nomograph

2\_2

po County Hydrology Manual use 2003

Table 3-1 RUNOFF COEFFICIENTS FOR URBAN AREAS

Section: Page:

			Runo	Runoff Coefficient "C"	**	
	I and Use			Soil Type	Ape	
		1		1	C	Q
		% IMPER.	Y	£		2.8.6
S Blements	County Elements	•	0.00	0.25	0.30	0.35
(Index) circles	Permanent Open Space	<b>,</b>	5.20	0.32	0.36	0.41
Undisturbed Natural Leading (1997)	Residential, 1.0 DU/A or less	01	0.27	0.38	0.42	0.46
Low Density Residential (LOS)	Residential, 2.0 DU/A or less	20	J. 0	0.41	0.45	0.49
Low Density Residential (LUK)	Series of DII/A or less	25	0.38	1.0	0.48	0.52
Low Deneity Residential (LDR)	Kesidenual, 2.3 Doi: 10.	30	0.41	0.45	0.40	23 0
" Density Residential (MDR)	Residential, 4.3 DU/A or less		0.48	0.51	0.54	0.57
Modern Land, Action (ADR)	Residential, 7.3 DU/A or less	0	£ 5 0	0.54	0.57	09:0
Medium Denaty Resolution (1925)	Desidential 10.9 DU/A or less	45	0.32	030	090	0.63
Medium Density Residential (MDK)		50	0.55	0.38		17.0
M. tiem Pensity Residential (MDR)	Residential, 14.5 DU/A of 1633	59	99.0	0.67	0.69	
The state of the s	Residential, 24.0 DU/A or less		92.0	0.77	0.78	0.79
High Dennis Assessed (HDB)	Residential, 43.0 DU/A or less	. 80	97.0	0.77	0.78	0.79
High Density Restoration (1997)	Neighborhood Commercial	08	08.0	0.80	0.81	0.82
	General Commercial	<b>C</b> 8 '	0.00	0.84	0.84	0.85
Commercial/Industrial (C. Com.)	Office Professional/Commercial	06	0.03	0.84	0.84	0.85
Commercial/Industrial (U.P. Com)	T Jodnetrial	06	0.83	· · ·	0.87	0.87
Commercial/Industrial (Limited I.)	רוני ווכת זוועתפים ייי	95	0.87	0.87	6.0	
Commorcial/Industrial (General I.)	General Industrial  General Industrial  General Industrial  General Industrial  General General Configuration of the runoff coefficient as described in Section 3.1.2 (representing the pervious runor)	ie runoff coefficien	t as described in	Section 3.1.2 (	representing the pain natural forevo	r (e.g., the area

1

•The values associated with 0% impervious may be used for direct calculation of the runoff coefficient as described in Section 3.1.2 (representing coefficient, Qp, for the soil type), or for areas that will remain undisturbed in perpetuity. Justification must be given that the area will remain natural is located in Cleveland National Forest).

DUNA - dwelling units per acre NRCS - National Resources Conservation Service



Table 7-14. Values of K' for Circular Channels in the Formula  $Q = \frac{K'}{n} d^{n/4} s^{1/2}$ 


D = depth of water


d = diameter of channel


$\left  \frac{\mathcal{L}}{d} \right $	.00	.01	.02	.03	.04	.05	.06	.07	.08	.09
.0 .1 .:2 .3	.00967 .04,06 .0907	.00007 .0118 .0448 .0966 .1633	.00031 .0142 .0492 .1027 .1705	.00074 .0167 .0537 .1089	.00138 .0195 .0585 .1153 .1854	.00222 .0225 .0634 .1218 .1929	.00328 .0257 .0686 .1284 .2005	.00455 .0291 .0738 .1352 .2082	.00604 .0327 .0793 .1420 .2160	.00775 .0366 .0849 .1490 .2238
.5 .6 .7 .8	.388 .458 .494	.239 .319 .395 .458 .496	.247 .327 .402 .463 .497	.255 .335 .409 .468 .498	.263 .343 .416 .473 .498	.271 .350 .422 .477 .498	.279 .358 .429 .481 .496-	.287 .366 .435 .485	.295 .373 .441 .488 .489	.303 .380 .447 .491 .483


# APPENDIX C


(6. HYDROLOGY MAP)











# ATTACHMENT G

# OPERATION AND MAINTENANCE PROGRAM FOR TREATMENT BMP

BMP OPERATIONT & MAINTENANCE		LABOR			EQUIPMENT	INT		MATERIALS	ØΙ.	TOTAL COST
ITEM	Per Hrs.	Rate	Cost	Туре	Days	Days Rate	Cost	ltem	Cost	
FILTER INSERTS	24.0	43.63	\$1,047.12	Sedan	2.0	2.0 21.28	\$42.56	\$42.56 New Adsorbent, Testing & Disposal	\$115.00	\$1,204.68
									O&M TOTAL	\$1,204.68

# ATTACHMENT H

# **CERTIFICATION SHEET**

This Stormwater Management Plan has been prepared under the direction of the following Registered Civil Engineer. The Registered Civil Engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.

HOSSEIN ZOMORRODI REGISTERED CIVIL ENGINEER DATE

